

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY  
508 EAST MURDOCK - WICHITA, KANSAS

*Plotted*  
*I.I.H.*  
Dupl.  
KGS

COMPANY THE CARTER OIL CO.

SEC. 13 T. 2 R. 14E

FARM Oreon Strahm

NO. 1

LOC. NW SW NW

TOTAL DEPTH 3929 3764 PB

COMM. 8-10-50

COMP. 9-7-50


SHOT OR TREATED

CONTRACTOR

ISSUED 3-3-51

COUNTY Nemaha

KANSAS



CASING

8 5/8" 180' cem. w/100 sx  
5 1/2" 3759' cem. w/300 sx

ELEVATION

*1254 RB 2nd*

PRODUCTION

388 BO 69 BW

FIGURES INDICATE BOTTOM OF FORMATIONS

surface clay	60
shale & sand	140
lime	181
lime & shale	230
shale & shells	810
lime & shale	1270
lime	1300
shale & lime	1475
lime & shale	1679
sandy shale	1725
sand & shale	1835
shale & sand	1994
sand & shale	2035
shale	2150
shale & sand	2226
shale	2366
shale, sand & chert	2419
lime & chert	2428
lime	2558
shale & shells	2585
shale	2700
shale & lime	2755
shale	2825
lime	3430
shale	3455
shale & lime	3495
lime	3711
lime & sand	3771
lime, sand & chert	3776
sand, iron & shale	3805
sand & shale	3809
lime	3907
sand	3927
granite	3929
Total Depth	PB to 3764

*3480*  
*1254*  
*2226*

*1571 H*

Tops;	
Howard	810
Topeka	845
Lansing	1264
Base Kansas City	1593
Miss. Chert	2412
Mississippi	2415
Kinderhook	2558
Hunton	2825
Maquoketa	3434
Viola	3480
Simpson	3737
Arbuckle-	3809
Granite	3927

Drugged back from 3929 to 3764'.