

9-2-14E ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BRUNSON SPINES
Farm- Mowder No. 1

SEC. 9 T. 2 R. 14 E
C NE NE

Total Depth. 3625'
Comm. 4-14-65 Comp. 4-24-65
Shot or Treated.
Contractor. Woodman & Iannitti
Issued. 5-29-65

County Nemaha
KANSAS



CASING:

8 5/8" 214' cem w/ 150 sx

Elevation. 1327' KB

Production. DRY

Figures Indicate Bottom of Formations.

clay	110
sand	125
shale & lime	215
shale	270
shale & shells	430
red bed	480
white sand	575
gray shale	825
shale & shells	1100
shale & lime	1225
lime & shale & sand	1420
lime	1570
lime & shale & sand	1785
lime & shale	2030
hard sand & shale	2165
lime & shale	2295
lime & sand	2410
shale	2440
sand & chert	2485
lime & chert & sand	2560
lime	2620
shale	2730
shale	2860
lime	2910
hard sand & lime	3010
sand chert & lime	3060
lime	3113
chert	3141
lime	3160
lime & chert	3220
lime	3320
sand & lime	3435
lime	3625 RTD
Total Depth	

DST #1 3586-90 Op 5 min pre-flow, shut in 30 min. Op 1 hr 20 min. Weak blow for 8 min and died. Shut in 30 min. Rec. 65' of fluid, including 5' of slightly oil cut mud and 60' of muddy water. IFP 19W; FP 38#, IBHP 1207#, FBHP 1188#.

TOPS: SMP	
Mississippi	2476
Kinderhook shale	2627
Hunton	2860
Maquoketa	3530
Viola	3585 good staining