

NATIONAL ASSOCIATED PETROLEUM CO.

Office Memorandum

From David A. Brierley

Date October 23, 1963

To Ferrest H. Lindsay

Subject #1 Fickle

50'W of NE NE NW
26-30-10E Elk County, Kansas

TYPE: Wildcat STATUS: D & A

ELEVATIONS: 1047' ground; 1052' K. B.

TOTAL DEPTHS: 2040' Driller; 2041' Schlumberger

PIPE: 8 5/8" set at 160' w/75 sx.

DATES: M. I. R. T. 10-10-63; D & A 10-14-63

SPECIAL TESTS: Drill Stem Tests

TOPS:

	SAMPLES	SCHLUMBERGER
B/Lansing	976	978
Drum Limestone	1128	1130
Layton sand	1136	1136
Dennis Limestone	1184	1185
Kansas City	1242	1246
B/Kansas City	1408	1410
Altamont	1506	1507
Pawnee	1602	1604
Ft. Scott	1658	1660
Miss	1980	1982

RESULTS OF SPECIAL TESTS:

#1 DST: 1984-2010: 30 min. I & FSIP, open 2 hours, strong blow, gas to surface in 3 minutes. Rec. 90' sour GCM w/oil scum in bottom. ISIP 731#, FSIP 706#, IFP 39#, FFP 50#, H. H. 1093#.

DAB:dc

Respectfully submitted,

David A. Brierley
David A. Brierley