

L S Well Service
543-A 22000 Rd.
Cherryvale, KS 67335
620-328-4433

DRILLER LOG

JAMES D. LORENZ

WESTERN LANDSC. #14
API#205-25586-00-00
SEC. 1, T30, R15E
WILSON CO, KS

0-150	LIME
150-255	SHALE
255-258	COAL
258-350	SHALE
350-480	LIME
480-517	SHALE
517-530	LIME
530-566	SHALE
566-628	LIME
628-745	SHALE
745-760	LIME PINK
760-797	SHALE
797-827	OSWEGO LIME
827-834	BLACK SHALE
834-844	LIME
844-849	BLACK SHALE
849-853	LIME
853-945	SHALE
945-947	LIME
947-949	COAL
949-985	SHALE
985-987	COAL
987-1020	SHALE
1020-1021	COAL
1021-1031	SANDY SHALE
1031-1177	SHALE
1177-1180	COAL
1180-1186	SHALE
1186-1188	COAL
1188-1219	SHALE
1219-1221	COAL
1221-1226	SHALE
1226-1239	MISSISSIPPI
	1239' T.D.

**2-27-03 Drilled 11 1/4" hole and set 21'
of 8 5/8" surface pipe and set with 6 sx.
of Portland cement.**

2-29-03 Started drilling 6 3/4" hole

2-29-03 Finished drilling to T.D. 1239'

**844' GAS TEST 0" ON 1/2" ORIFICE
849' COAL**

863' GAS TEST 20" ON 1/2" ORIFICE

1189' GAS TEST 4 1/2LB. ON 3/4" ORIFICE

**1230-1242' ODOR
1238-1242' BROWN LIME -ODOR
1250' GREEN SHALE**