

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 33074
Name: Dart Cherokee Basin Operating Co., LLC
Address: P O Box 177
City/State/Zip: Mason MI 48854-0177
Purchaser: Oneok
Operator Contact Person: Beth Oswald
Phone: (517) 244-8716
Contractor: Name: McPherson
License: 5675
Wellsite Geologist: Bill Barks
Designate Type of Completion:
☒ New Well ☐ Re-Entry ☐ Workover
☐ Oil ☐ SWD ☐ SIOW ☐ Temp. Abd.
☒ Gas ☐ ENHR ☐ SIGW
☐ Dry ☐ Other (Core, WSW, Expl., Cathodic, etc)
If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
☐ Deepening ☐ Re-perf. ☐ Conv. to Enhr./SWD
☐ Plug Back ☐ Plug Back Total Depth
☐ Commingled ☐ Docket No. _____
☐ Dual Completion ☐ Docket No. _____
☐ Other (SWD or Enhr.?) ☐ Docket No. _____

3-24-03	3-27-03	4-10-03
Spud Date or	Date Reached TD	Completion Date or
Recompletion Date		Recompletion Date

API No. 15 - 205-25572-00-00
County: Wilson
W2 SE SE Sec. 36 Twp. 30 S. R. 15 ☒ East ☐ West
550 FSL feet from S / N (circle one) Line of Section
1000 FEL feet from E / W (circle one) Line of Section
Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Small Well #: D4-36
Field Name: Neodesha
Producing Formation: Penn Coals
Elevation: Ground: 829' Kelly Bushing: _____
Total Depth: 1264' Plug Back Total Depth: 1260'
Amount of Surface Pipe Set and Cemented at 20 Feet
Multiple Stage Cementing Collar Used? ☐ Yes ☒ No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan

(Data must be collected from the Reserve Pit)

Chloride content NA ppm Fluid volume 240/160 bbls
Dewatering method used empty w/ vac trk and air dry
Location of fluid disposal if hauled offsite: _____
Operator Name: Dart Cherokee Basin Operating Co, LLC
Lease Name: SSR D2-20/Adee B' License No.: 33074
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: Montgomery Docket No.: D28214/D28237

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Beth Oswald
Title: Admn & Engr Asst Date: 2-17-04
Subscribed and sworn to before me this 17th day of February, 2004.
Notary Public: Karen L. Welton
Date Commission Expires: _____

Karen L. Welton
Notary Public, Ingham County, MI
My Comm. Expires Mar. 3, 2007

KCC Office Use ONLY

☐ Letter of Confidentiality Attached
If Denied, Yes ☐ Date: _____
☐ Wireline Log Received
☐ Geologist Report Received
☐ UIC Distribution

Operator Name: Dart Cherokee Basin Operating Co., LLC Lease Name: Small Well #: D4-36
 Sec. 36 Twp. 30 S. R. 15 ☒ East ☐ West County: Wilson

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken ☐ Yes ☒ No
 (Attach Additional Sheets)

Samples Sent to Geological Survey ☐ Yes ☒ No

Cores Taken ☐ Yes ☒ No

Electric Log Run ☒ Yes ☐ No
 (Submit Copy)

List All E. Logs Run:

High Resolution Compensated Density Neutron

Log Formation (Top), Depth and Datum ☒ Sample
 Name Top Datum
 See Attached

RECEIVED
FEB 20 2004
KCC WICHITA

CASING RECORD							
				New	Used		
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surf	11"	8 5/8"		20'	Class A	4	
Prod	6 3/4"	4 1/2"	10.5	1260'	50/50 Poz	165	

ADDITIONAL CEMENTING / SQUEEZE RECORD

Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
☐ Perforate				
☐ Protect Casing				
☐ Plug Back TD				
☐ Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
6	1090'-1092, CIBP set @ 1070'	1000 gal 12% HCl, 3300# sd, 440 BBL fl	
6	943.5'-944.5'	500 gal 12% HCl, 100# sd, 330 BBL fl	
6	900'-901.5'	1000 gal 12% HCl, 2510# sd, 420 BBL fl	
6	759'-761'	750 gal 12% HCl, 3355# sd, 445 BBL fl	
6	724'-728.5'	750 gal 12% HCl, 7225# sd, 725 BBL fl	
TUBING RECORD		Liner Run	
Size	Set At	Packer At	Yes ☒ No
2 3/8"	1036'	NA	
Date of First, Resumed Production, SWD or Enhr.		Producing Method	
11-27-04		Flowing ☒ Pumping ☒ Gas Lift ☐ Other (Explain)	
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.
	NA	25	60
Gas-Oil Ratio		Gravity	
NA		NA	

Disposition of Gas

METHOD OF COMPLETION

Production Interval

☐ Vented ☒ Sold ☐ Used on Lease
 (If vented, Submit ACO-18.)

☐ Open Hole ☐ Perf. ☐ Dually Comp. ☐ Commingled
☐ Other (Specify) _____