

L AND S WELL SERVICE
543A 22000 ROAD
CHERRYVALE, KS 67335
620-328-4433

DRILL LOG
BAILEY OIL CO.

KIMBALL-12-K
API#15-205-25574-00-00
2440' FSL, 2350' FWL
Wilson County, KS
S19, T30, R16E

0-12	DIRT	10-26-02 Drilled 11 1/4" hole and set 45' of 7"
12-15'	CLAY	Surface pipe with 30 sacks of Portland cement.
15-30	RIVER GRAVEL	10-28-02 Started drilling 6 1/4" hole
30-110	SHALE	10-28-02 Finished drilling to T.D.
110-122	LIME	
122-140	SHALE	
140-192	LIME	170' WATER
192-198	BLACK SHALE/GAS ODOR	185' GAS TEST 0" ON 1/2" ORIFICE
196-200	LIME	200' GAS TEST 3" ON 1/2" ORIFICE
200-225	SHALE	
225-235	SANDY SHALE	
235-240	SHALE	
240-242	COAL	
242-250	SHALE	245' GAS TEST 2" ON 1/2" ORIFICE
250-254	SAND	
254-260	SHALE	
260-280	LIME	
280-292	BLACK SHALE	
292-322	SHALE	310' GAS TEST 1" ON 1/2" ORIFICE
322-336	LIME	
336-344	BLACK SHALE	
344-385	SHALE	350' GAS TEST 3" ON 1/2" ORIFICE
385-430	LIME	362' STARTED INJECTING WATER
430-435	BLACK SHALE	
435-452	SAND W/ODOR	445' OIL ON PIT
452-462	LAMINATED SAND	
462-484	SHALE	
484-530	SAND	512' GAS TEST 3 1/2" ON 1/2" ORIFICE
530-535	SANDY SHALE	
535-565	SHALE	
565-566	COAL	
566-570	SHALE	
570-590	PINK LIME	
590-596	BLACK SHALE	
596-608	SAND	
608-611	SHALE	
611-617	SAND	
617-637	SHALE	
637-665	LIME	660' GAS TEST 3" ON 1/2" ORIFICE
665-672	BLACK SHALE	
672-680	COAL	673' GAS TEST 3" ON 1/2" ORIFICE
680-686	SHALE	
686-690	COAL	688' GAS TEST 5" ON 1/2" ORIFICE
690-698	SHALE	
698-700	COAL	
700-725	SHALE	713' GAS TEST 4" ON 1/2" ORIFICE
725-726	COAL	
726-737	SHALE	

L AND S WELL SERVICE
543A 22000 ROAD
CHERRYVALE, KS 67335
620-328-4433

DRILL LOG

BAILEY OIL CO.

KIMBALL-T2-K
API#15-205-25574-00-00
2440' FSL, 2350' FWL
Wilson County, KS
S19, T30, R16E

737-739	LIME
739-740	COAL
740-753	SANDY SHALE
753-783	SHALE
783-784	COAL
784-814	SHALE
814-820	SAND/ODOR/OIL
820-844	SHALE
844-860	SAND/ODOR/OIL
860-885	SHALE
885-886	COAL
886-904	SHALE
904-906	COAL
906-938	SHALE
938-1042	SAND
1042-1064	SHALE
1064-1067	COAL
1067-1080	SHALE
1080-1089	MISSISSIPPI
1089'	T.D.

939' GAS TEST 6" ON 1/2" ORIFICE
984' GAS TEST 16" ON 1/2" ORIFICE
1005' GAS TEST 25" ON 1/2" ORIFICE