

State Kansas County Sumner

Company Messman-Rinehart Oil Co. Well No. 2

Farm Winstead


Survey

Block No. Sec. 17 Twp. 30 S Range 1 E

Co-Ord. Elev. 245 K/B
242 D/F
239 Gr

SE SE SW

M-R Rig



$\frac{1}{4}$ - Messman-Rinehart Oil Co.

$\frac{1}{4}$ - Chicago Group

$\frac{1}{2}$ - A. L. Becker

($\frac{1}{4}$ A.A. Seeligson Jr.)

ORI - Marjorie S. Waite

FO 3-3034

3850' Sp. Sd. Test

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line 330 Ft. from S. Line

2310 Ft. from W. Line Ft. from E. Line

Date	Depth	
1/13/58		Staked
1/24/		M.I.R.T.
1/25		Spudded - 8-5/8" @ 293'
		w/200 sx. cem., 4 gal, 4 cc
		PD @ 11:30 P.M. 1/25/58
1/28	1335'	Drlg.
1/29	1900'	Drlg.
1/30	2305'	Drlg. (#4 bit going in hole)
1/31	2715'	Making a trip

692748

Date	Depth	
	2778'	K.C. (-1533) (flat w/#1 Seydel)
	2795'	Drlg.
2/1	3000'	Drlg. (strapped DP - OK) (#6 bit @ 2978)
2/2	3240'	Drlg. (#7 @ 3240) (9 dr. collars 2-3"/ft)
2/3	3460'	Drlg. (#8 @ 3409)
		(6-12"/ft. in Miss.)
2/4	3596'	Drlg. (#9 bit @ 3485)
		(#10 bit @ 3551)
		(#11 bit @ 3596)
2/5	3390'	Miss. (-2145) (#12 bit @ 3656)
	3672'	(lost circu.)
	3681'	(lost circu.)
	3702'	(regained circ. & put on #13 bit (#14 bit @ 3776)
	3778'	Kinderhook (-2533)
	3790'	Chattanooga (-2545)
2/6	3827-3857	Cored (16½% poro., 11.7' very good saturation Sp. sd. (-2587)
	3832'	
	3875'	R.T.D.
2/7		5½" @ 3875' w/80 sx. posmix PD @ 4:00 P.M. 2/7/58
		(no log)
2/15/58		M.I.C.T. - Perf. 3835-38 w/4s per ft. - all water
2/17		Fishing for swb. tools

State Kansas County Sumner

Company Messman-Rinehart Oil Co. Well No. 2

Farm Winstead


Survey _____

Block No. _____ Sec. 17 Twp. 30 S Range 1 E

Co-Ord. _____ Elev. 1245 K/B
1242 D/F

SE SESW

M-R Rig 1239 Gr



Page 2

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line 330 Ft. from S. Line _____

2310 Ft. from W. Line _____ Ft. from E. Line _____

Date	Depth	
2/18/58		Set bridging plug @ 3480'
		Sq. @ 2616', pressured up to
		2000# & didn't displace any
		Swb. down to 3480', retrieved
		plug, Swb. hole clean
2/20		Recovered swab tools
2/21		Sq. Perf. 3835-38 w/300 gal.
		ceo-mint (Dow Compound)
2/24		DOC (preparing to perf.)

[illegible]