

Rig #:	One				
API No:	15-133-25950-0000				
Operator:	Quest Energy Services, Inc.				
Address:	PO Box 100				
	Benedict, KS 66714				
Well No:	6-1	Lease Name:	Baker		
Footage Location:	1,320	feet from the	S	Line	
	1,680	feet from the	E	Line	
Contractor:	Well Refined Drilling Company, Inc., Contractor #33072				
Spud Date:	27-Mar-03	Geologist:	Mike Ebers		
Date Completed:	21-Mar-03	Total Depth:	1183		

S.6	T.30	R.18
Location:	SE 1/4	
County:	Neosho	

Gas Tests			
Depth	Oz.	Orifice	Flow (mcf)
623	1.0	0.375	3.560
643	1.0	0.375	3.560
663	1.0	0.375	3.560
708	3.0	0.375	6.180
723	5.0	0.375	7.980
783	9.0	0.375	10.700
823	10.0	0.375	11.300
863	10.0	0.375	11.300
923	2.0	0.375	5.050
963	3.0	0.375	6.180
1063	3.0	0.375	6.180
1083	3.0	0.375	6.180
1123	3.0	0.375	6.180
1143	3.0	0.375	6.180

Casing Record		
	Surface	Production
Size Hole:	12.250	6.750
Size Casing:	8.625	
Weight:		
Setting Depth:	23.5	
Type Cement:	Portland	
Sacks:	4	
Elevation:		



Rig Time	Work Performed

Well Log								
Formation	Top	Bottom	Formation	Top	Bottom	Formation	Top	Bottom
Overburden	0	2	Shale	450	464	Oswego Lime	675	698
Clay	2	4	Lime	464	484	Shale	698	700
Sand	4	20	Shale	484	507	Black Shale	700	703
Lime	20	23	Sand	507	515	Shale	703	706
Shale	23	33	Shale	515	588	Lime	706	715
Sand Wet	33	57	Coal	588	589	Black Shale	715	720
Shale	57	185	Shale	589	593	Coal	720	721
Lime	185	241	Pink Lime	593	617	Lime	721	725
Black Shale	241	246	Shale	617	619	Shale	725	779
Water	241	246	Lime	619	623	Coal	779	780
Lime	246	287	Black Shale	623	626	Shale	780	799
Shale	287	290	Shale	626	649	Lime	799	801
Black Shale	290	294	Sand	649	670	Shale	801	803
Lime	294	367	Oil Show	649	664	Black Shale	803	804
Shale	367	429	Oil on Pit	661		Coal	804	805
Lime	429	431	Oil Odor	664		Shale	805	834
Shale	431	439	Coal	670	671	Sand	834	838
Lime	439	450	Shale	671	675	Shale	838	841

AUG 04 2001
 KCC WICHITA

COPY

Lease & Well #: Baker 6-1

Well Log

Formation	Top	Bottom	Formation	Top	Bottom	Formation	Top	Bottom
Coal	841	842						
Shale	842	856						
Coal	856	857						
Shale	857	913						
Coal	913	914						
Shale	914	935						
Sand	935	940						
LA Sand	940	942						
Shale	942	951						
Coal	951	952						
Shale	952	1058						
Coal	1058	1060						
Shale	1060	1065						
Coal	1065	1066						
Shale	1066	1115						
LA Sand	1115	1119						
Coal	1119	1121						
Shale	1121	1133						
Chat	1133	1134						
Lime	1134	1183						
TOTAL DEPTH	1183							

Rig Time	Work Performed

Driller	
Helper #1	
Helper #2	
Helper #3	
Helper #4	