

24-30-20E

Company

Sec. 24 T. 30 R. 20E

Farm Snider

No.

Loc. NE NW

County Neosho

Total Depth 651'


Comm.

Comp.

Shot or Treated

Contractor

Issued



Casing	
20 in.	10 in.
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16

Elevation 875± from topog map

Production

Figures Indicate Bottom of Formation

0 - 16	16	sandstone		
16 - 19	3	dark shale		
19 - 23	4	lime		
23 - 65	42	dark gray shale--lime shells	38' wtr	
65 - 75	10	black shale		
75 - 105	30	lime	Pawnee	105
105 - 115	10	black shale		
115 - 122	7	light gray shale		
122 - 125	3	lime		
125 - 140	15	sandy shale		
140 - 147	7	dark gray shale		
147 - 158	11	black shale		
158 - 181	23	lime	Ft Scott	158
181 - 188	7	black shale break	188 wtr	198
188 - 198	10	lime		
198 - 203	5	black shale	203 wtr	
203 - 206	3	lime		
206 - 222	16	light gray shale		
222 - 305	83	lime and black shale stratas		
305 - 310	5	light gray shale and lime		
310 - 328	18	black shale--lime shells		
328 - 365	37	gray shale		
365 - 375	10	black shale		
375 - 440	65	black shale--occasional thin lime strata		
440 - 475	35	light gray shale		
475 - 497	22	varied colored shales, changing from white to blue to black	497 wtr	
497 - 560	63	black shale		
560 - 570	10	light gray shale		
570 - 625	55	black shale		
625 - 632	7	light gray shale		
632 - 644	12	black shale	} gas	
644 - 651	7	white and blue flint--gray sand (gas)		

gas 646' - 628'

water 38' - 188' - 203' - 497'