

V W & B DRILLING CO.

Box 7 N. Hwy. 169
CHERRYVALE, KS 67335Inco Energy, Inc.
P. O. Box 379
Parsons, Kans. 67357
Hiller Well #34
Commenced Drilling 2-7-84
Completed Drilling 2-13-84SESENE 34-30-21
v Neosho County

Top Soil	0	1
Gray Clay	1	9
Yellow Clay	9	13 Water
Shaley Limestone	13	15
Limestone	15	26
Blk Shale	26	30
Gray Shale	30	32
Limestone	32	44
Blk Shale	44	49
Gray Shale	49	55
Siltstone	55	60
Silty Gray Shale	60	70
Gray Shale	70	125
Dk Gray Shale	125	131
Coal	131	132 Water
Gray Shale	132	141
Limestone	141	142
Blk Shale	142	143
Limestone	143	144
Blk Shale	144	149
Streak of Coal	149	
Gray Shale	149	160.5
Sandstone	160.5	167 Water & Oil
Bottom of Hole	167	

21' 7" casing cemented with 5 sacks portland cement 10# calcium Chloride

159' 4" casing cemented ~~XXXX~~ in hole by ConsolidatedHole size ~~XXXX~~ 10" to 21'

Hole size 6½" to bottom of hole