

COPY

VW & B DRILLING CO.
Box 7 N. Hwy 143
Cherryvale, KS 67535

Hiller Farm Well # 25

Sec. 34 T30S R21E
Loc. NE of NE 200 feet
from east line,
1200 feet from
north line.

Drilled for Hickory Creek Oil Company

Began 12-13-79

Completed 12-15-79

Figures indicate bottom of formation

1	Top Soil	1	1	Lime	152	152
12	Yellow Clay	13	5	Blk. Shale		157
2	River Gravel	15	10	Lt. Shale		167
8	Lime	23	5	Med. Shale		172
5	Blk. Shale	28	66	Bartlesville		
5	Lime	33		Sand	238	
1	Blk. Shale	34	1	Coal	239	
9	Lime	43	5	Coal & Sand	244	
3	Blk. Shale	46	22	Med. Shale	262	
1	Lime	47	10	Lt. Shale	272	
13	Lt. Shale	60	6	Med. Shale	278	
78	Med. Shale	138	3	Lt. Shale	281	
1	Coal	139	1	Red Shale	282	
10	Med. Shale	149	9	Grn. Shale	291	
1	Lime	150	11	Med. Shale	302	
1	Blk. Shale	151				

20 feet of 7 inch casing set with
6 sacks of cement. Hole size 6 1/4
to 302 feet. 285 feet 2 inch of
1/2 inch casing set with float shoe.
Bottom centerlizer set at 252 feet.
Top centerlizer set at 165 feet.