


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

31-30-22E

Company- DONALD P. OAK  
Farm- Gregg No. 11

SEC. 31 T. 30 R. 22E  
SW SE NW NW  
4250' N & 920' E of SW corner

County Crawford  
KANSAS



Total Depth. 263  
Comm. 11-26-52 Comp. 12-6-52  
Shot or Treated.  
Contractor. Karl Houseweart  
Issued. 12-20-52

Elevation. \_\_\_\_\_  
Production Est. 10 bbls

CASING:  
6 1/4" 20'  
2" line pipe 231' cem w/37 sx

Figures indicate Bottom of Formations.

soil, clay	20
lime	39
shale black	44
lime	58
shale black	64
lime	66
shale light	147
shale dark	157
lime shells	165
shale light	185
shale dark	201
shale light	220
shale sandy, light	
Show of oil	229
sand Oil	261
sand Oil pocket	263

N - 5324 4250-FSL  
S - 5285 4365-FEL  
E - 5323 SW SE NW NW  
W - 5345

(KGS DEL NOV 83 2022)

Shot: 12-4-52 Larkin Torpedo  
Co.: 233 -247 3" shell 20 qts.  
247 -257 3 1/2" " 20 "  
Total 40 qts

Total Depth 263

Sand Record:  
Bartlesville Sand 233 - 263