

Company McCune Oil & Gas Co.

31- 30- 2 2 E  
Sec. 31 T. 30 R. 22 E

Loc. SW NW

County Crawford

Farm A. B. Gregg

No. 11

Total Depth 513

Comm. June 20, 1930

Comp. June 23, 1930


Shot or Treated

Contractor W. W. Kaney

Issued

Casing

|                |            |
|----------------|------------|
| 20 in.         | 10 in.     |
| 15 1/2         | 8 1/4      |
| 12 1/2         | 6 5/8      |
| 13 3/8         | 5 3/16     |
| 6 3/4 26'      | 4 7/8 185' |
| 2" tubing 510' |            |
| Casings pulled |            |



Elevation 894

Packer set at 484; cage set at 50

Production

Figures Indicate Bottom of Formation

|                |                             |
|----------------|-----------------------------|
| soil & clay    | 26                          |
| shale          | 30                          |
| lime           | 49                          |
| shale          | 54                          |
| lime           | 70                          |
| shale          | 76                          |
| lime           | 78                          |
| shale          | 172                         |
| sand shells    | 185                         |
| shale          | 232                         |
| sand & shale   | 240                         |
| sand           | 268                         |
| shale          | 487                         |
| sand           | 498                         |
| B. Shale       | 500                         |
| pyrite of iron | 506                         |
| Miss. lime     | 513 gas in top incr. to 509 |

Water at 509 or 510. Rubberless packer set just above cage. Cage set 5' up from bottom. Well tests 281,000 after plugging back 4' plug in bottom.