

Company McCune Oil & Gas Company


Farm A. B. Gregg

No. 4

31-30-22E
Sec. 31 T. 30 R. 22 E
Loc. NW NE NW
County Crawford

Total Depth 508
Comm. April 18, 1930
Shot or Treated
Contractor W. W. Kaney
Issued

Comp. April 22, 1930



Casing	
20 in.	10 in.
15 1/2	8 1/4
12 1/2	6 5/8 1/4 33'
13 3/8	5 3/16

Elevation 881

Production

4 7/8 192'
Packer set at 488
Figures Indicate Bottom of Formation

soil and clay	23
lime	43
shale	48
lime	61
shale	160
lime	164
shale	174
sand	176 a little gas
shale	180
sand	183
shale	203
sand	206
sand	213 a little gas
shale	228
oil sand	248 small show of oil in top incr. to 223
shale	485
black shale	
iron pyrites	503
Chat. lime	507 gas in top incr. to 507
hard fine lime	508

Cage 4' from bottom; rubberless packer set on top of cage.