


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

31-30-22E

Company- DONALD P. OAK
Farm- Houseweart No. 7

SEC. 31 T. 30 R. 22E
1610' N & 250' E of SW
Corner
SW SW NW SW
County Crawford
KANSAS

Total Depth. 259½'
Comm. 1-12-54 Comp. 1-27-54
Shot or Treated.
Contractor.
Issued. 2-27-54



Elevation. _____

Production. Est. 6 Bbls.

Figures indicate Bottom of Formations.

soil & clay	21
lime	38
shale	44 little water
lime	60
shale black	65 more water plenty to drill with
lime	66
shale light	150
lime shells	170 hard shell @ 207'
shale	220 smell of oil at 212'
sand broken	223 water & oil (2½ bailers in 15
dark sand	228 minutes) at 217'9" increase in fluid
fine dark sand	233'6" showed good oil
dark sand, coarser	237 good show of oil
sand, light fine	241
dark brown sand	246
sand darker brown	251
dark sand	256 shows very little oil
real dark sand	259
TD	259½
Total Depth	

1610 FSL
5285-250=5,035 FSL
SW SW NW SW
KGS-OIL NAD83
LEO web
10/12/2022

Tops:
Bartlesville sand 223-259

sandfraced from 233'6" to 237 with 4000 lbs. sand and 3000 gallons Petrofrac.

S.L.M @ 217'9"
4 7/8" hole to 259½'
Tubed with new 2" C.W. line pipe (bought from National Supply Co.),
and 5/8" suckers from lease.