

Company Max B. Miller & Co., Inc.

19-30-225

Farm Bevins N No. C (Input)

Total Depth 262'

Sec. 19 T. 30 R. 22

Comm. 10-25-39

Comp. 10-27-39

Loc. NW-NW*NE

County Crawford

Elevation 897.5

Production

Figures Indicate Bottom of Formation

Rocks and soil	0	2	2
Soft dark shale	2	15	13
Soft light shale	15	58	43
Soft dark shale	58	75	17
Hard light lime	75	90	15
Soft dark shale	90	95	5
Hard light lime	95	107	12
Soft dark shale	107	111	4
Soft light shale	111	190	79
Soft dark shale	190	207	17
Soft light shale	207	210	3
Hard light lime	210	212	2
Hard black shale	212	217	5
Soft light shale	217	221	4
Soft dark shale	221	227	6
Soft light shale	227	262	35

Company Max B. Miller & Co., Inc.

19-30-22E

Farm Bevins N No. C. (Input)

Total Depth 262'

Sec. 19 T. 30 R. 22

Comm. 10-25-39

Comp. 10-27-39

Loc. NW-NW-NE

County Crawford

Elevation 897.5'

Production

Casing

125' 6 5/8"
315 2

Shot or Treated

11-1-39	75qts Gelatine	284' to 295'	Shells size 3 x 11	10qts
		295 315	5 20	65"
	Squib shot Gelatine	308 315		

Plug Back Record

Well not drilled through sand.

Packers

Rag packer run on 2" SH tubing set at 287'. Eight sacks cement on packer.

Clean-Out Record

11-1-2-3-39 Cleaned with Larkin Sand Pump.

August 1940 well filled with sand 303' to 315'. Cement injected through 2" tubing until rate of take was 0. Cement allowed to set 30 hours. 1 3/4" hole drilled through cement and sand was flushed out.