

Company Max B. Miller & Co., Inc.

14-30-225

Farm Bevins N. No. x1 (Input)

Total Depth 310'

Sec. 19 T. 30 R. 22

Comm. 5-26-37

Comp. 5-28-37

Loc. 660' from E. line
200' from N. line
of NE $\frac{1}{4}$ of Sec. 19.

County Crawford

Elevation 892'

Production Dry

↓
NE NE
KGS-ORL

Figures Indicate Bottom of Formation

Soil	0	2	2
Clay & Boulders	2	10	8
Med. Grey Sandy Shale	10	40	30
Soft Blue Shale	40	56	16
Hard Light Lime	56	75	19
Hard Black Shale	75	80	5
Hard Light Lime	80	85	5
Hard Dark Lime	85	93	8
Hard Black Shale	93	95	2
Hard Black Shale	95	100	5
Soft Light Shale	100	105	5
Soft Dark Shale	105	108	3
Soft Blue Shale	108	138	30
Soft Light Shale	138	180	42
H. Dark Lime & shale			
Shells	180	195	15
Hard Dark Lime	195	198	3
Soft Black Shale	198	200	2
Hard Dark Lime	200	202	2
Soft Dark Shale	202	215	13
Soft Light Shale	215	227	12
Hard Grey Lime	227	229	2
Soft Dark Shale	229	235	6
Soft Blue Shale	235	245	10
Soft Light Sandy Shale	245	250	5
Med. Light Sandy Shale	250	290	40
Soft Dark Shale	290	295	5
Soft Black Shale	295	300	5
Soft Light Shale	300	310	10

Company Max B. Miller & Co., Inc.

19-30-225

Farm Bevins N.

No. x1 (Input)

Total Depth 310'

Sec. 19 T. 30 R. 22

Comm. 5-26-37

Comp. 5-28-37

Loc. 660' from E line
200' from N line
of NE $\frac{1}{4}$ of Sec. 19.

County Crawford

Elevation 892'

Production Dry

Casing

108'

310'

Plugging Record

5-28-37--5-28-37. 5 $\frac{1}{2}$ sacks of cement and 400 lbs sand used.
Approximate top of cement 240'. Mudded from 240' to top of hole.
No pipe left in hole.

250'--290' 40' Medium light sandy shale. No trace of oil shown.
Black shale showing at bottom at 310' run.