

Company Max B. Miller & Co., Inc.

19-30-22E

Farm Bevins N. No. 2B (Test)

Total Depth 313'

Sec. 19 T. 30 R. 22

Comm. 12-19-39

Comp. 12-26-39 Loc. 375' from N line
225' from W line
of NE $\frac{1}{4}$ of Sec. 19

County Crawford

Elevation 897.8

Production

NW NW NE
KGS + DRL
NW SE NE
KGS DRL LO
NW NE DRL

Figures Indicate Bottom of Formation

Soft Dark Shale	13	15	2
Soft Light Shale	15	55	40
Soft Dark Shale	55	72	17
Hard Dark Lime	72	90	18
Soft Dark Shale	90	94	4
Hard Light Lime	94	107	13
Soft Dark Shale	107	155	48
Soft Light Shale	155	189	12
Soft Dark Shale	189	202	3
Soft Light Shale	202	205	3
Hard Dark Lime	205	206	1
Soft Dark Shale	206	215	9
Soft Light Shale	215	220	5
Soft Light Shale	220	273	53
Sand Cored	274	313	39

Fluid used in making a twenty-five minute test on sand.

3 gallon	276'	6"	279'	9"
2 bailers good show of oil	279	9	282	4
1 $\frac{1}{4}$ bailer 2 gallons	282	4	285	8
1 bailer 2 gallons	285	8	288	8
1 bailer 2 gallons	288	8	291	4
Changed to small bailer				
2 pc. small bailer	294	4	297	4
	297	4	300	4
	300	4	303	8
	303	8	306	10
	306	10	310	
	310		313	

2 pc. small bailer would equal tests above showing no increase in fluid.

Company Max B. Miller & Co., Inc.

19-30-22E

Farm Bevins N No. 2B (Test Well)

Total Depth 313'

Sec. 19 T. 30 R. 22

Comm. 12-19-39

Comp. 12-26-39

Loc. 375' from N line
225' from W line
of NE $\frac{1}{4}$ of Sec. 19

County Crawford

Elevation 897.8

Production

Casing

13' 8"

273 6 5/8

313 2

Shot or Treated

1-17-40 45qts Gelatine 299' to 313' Shells size 5" x 14' Elec.
anchor

Packers

Anchor pumping packer run on 2" tubing set at 296'.

Clean-Out Record

1-19-20-21-22-23-24-25-26-40 Lark in sand pump Well caved a large amount of sand. Morning of Jan 26, 1940 well had not caved after setting for 18 hours.

Jan. 17, 1940 Shot well with 45qts of gelatine, sand tamped with 2500 lbs sand at 273'--6 5/8" casing in well. 200ft of casing was lifted out of the well, which broke off in sections as it fell.

6 5/8" casing replaced with 6 $\frac{1}{4}$ " casing.