

Company Max B. Miller & Co., Inc.

Farm Bevins S No. x18 (Input)

Total Depth 270'

Sec. 19 T. 30 R. 22

Comm. 6-1-38

Comp. 6-6 38

Loc. 20' from N line  
360 from W line  
of SW $\frac{1}{4}$ -NE $\frac{1}{4}$

County Crawford

Elevation 904.0'

Production

Figures Indicate Bottom of Formation

Soil and clay	0	7	7
Soft light shale	7	40	33
Soft dark shale	40	69	29
Lime	69	86	17
Hard blue shale	86	90	4
Hard black shale	90	91	1
Lime	91	104	13
Hard black shale	104	110	6
Soft light shale	110	195	85
Soft dark shale	195	200	5
Soft light shale	200	210	10
Dark lime	210	214	4
Soft light shale	214	220	6
Soft dark shale	220	235	15
Soft light shale	235	270	35

Company Max B. Miller & Co., Inc.

19-30-22E

Farm Bevins S. No. x18 (Input)

Total Depth 270'

Sec.19 T. 30 R. 22

Comm. 6-1-38

Comp. 6-6-38

Loc. 20' from N line  
360 from W line  
of SW $\frac{1}{4}$ -NE $\frac{1}{4}$

County Crawford

Elevation 904.0'

Production

↓  
NW SW NE  
1 FE  
KGS DRL

Casing

115' 6 5/8"  
318 2

Shot or Treated

6-15-38 62 qts Gelatine 287' to 301' Shells size 4" x 15' 22qts  
Electric bomb 301 314 5 13 40 "

Plug Back Record

6-18-38 Straight cement 318' to 314'. Cement placed in bottom of well with dump bailer.

Packers

Rag packers run on 2" tubing set at 287'. 6 $\frac{1}{2}$  sacks cement on packer.

Clean-Out Record

6-16-17-38 Both bailer and tools used. Well thoroughly washed and cleaned.