

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 33074
Name: Dart Cherokee Basin Operating Co., LLC
Address: P O Box 177
City/State/Zip: Mason MI 48854-0177
Purchaser: Southern Star

Operator Contact Person: Beth Oswald
Phone: (517) 244-8716
Contractor: Name: Kephart Drilling Inc.
License: 5379

Wellsite Geologist: John W Smith

Designate Type of Completion:

☐ New Well ☐ Re-Entry ☒ Workover
☐ Oil ☐ SWD ☐ SIOW ☐ Temp. Abd.
☒ Gas ☐ ENHR ☐ SIGW
☐ Dry ☐ Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:

Operator: Dart Cherokee Basin Operating Co., LLC

Well Name: Botts 3

Original Comp. Date: 1-5-91 Original Total Depth: 1072'

☐ Deepening ☒ Re-perf. ☐ Conv. to Enhr./SWD

☐ Plug Back ☐ Plug Back Total Depth

☐ Commingled ☐ Docket No. _____

☐ Dual Completion ☐ Docket No. _____

☐ Other (SWD or Enhr.?) ☐ Docket No. _____

11-20-02 10-30-90 11-24-02

Spud Date or
Recompletion Date Date Reached TD Completion Date or
Recompletion Date

API No. 15 - 125-29325-00-01

County: Montgomery

SW NE SE Sec. 18 Twp. 31 S. R. 16 ☒ East ☐ West

1810' FNL feet from S / N (circle one) Line of Section

990' FWL feet from E / W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:

(circle one) NE SE NW SW

Section Name: Botts Well #: 3

Field Name: Neodesha

Producing Formation: Penn Coals

Elevation: Ground: 772' Kelly Bushing: _____

Total Depth: 1072' Plug Back Total Depth: 1058'

Amount of Surface Pipe Set and Cemented at 40' Feet

Multiple Stage Cementing Collar Used? ☐ Yes ☒ No

If yes, show depth set _____ Feet

If Alternate II completion, cement circulated from 1070'

feet depth to surf w/ 118 sx cmf.

Drilling Fluid Management Plan Wheeler on 4-25-03
(Data must be collected from the Reserve Pit)

Chloride content _____ ppm Fluid volume _____ bbls

Dewatering method used _____

Location of fluid disposal if hauled offsite: _____

Operator Name: _____

Lease Name: _____ License No.: _____

Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West

County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Beth Oswald

Title: Engr Asst Date: 4-15-03

Subscribed and sworn to before me this 15th day of April

15 2003.

Notary Public: Karen L. Welton

Date Commission Expires: Karen L. Welton

Notary Public, Ingham County, MI

KCC Office Use ONLY

N Letter of Confidentiality Attached

If Denied, Yes ☐ Date: _____

N Wireline Log Received

N Geologist Report Received

____ UIC Distribution

Operator Name: Dart Cherokee Basin Operating Co., LLC Lease Name: Botts Well #: 3
 Sec. 18 Twp. 31 S. R. 16 ✓ East West County: Montgomery

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken ☐ Yes No (Attach Additional Sheets) Samples Sent to Geological Survey ☐ Yes No Cores Taken Yes No Electric Log Run Yes No (Submit Copy) List All E. Logs Run: <u>Wire log ACO-1</u> High Resolution Compensated Density Neutron	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="width: 20%;">Log</th> <th style="width: 40%;">Formation (Top), Depth and Datum</th> <th style="width: 40%;">✓ Sample</th> </tr> <tr> <th>Name</th> <th>Top</th> <th>Datum</th> </tr> </table>	Log	Formation (Top), Depth and Datum	✓ Sample	Name	Top	Datum
Log	Formation (Top), Depth and Datum	✓ Sample					
Name	Top	Datum					

CASING RECORD							
New				Used			
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surf	8 5/8"	7"		40'	Common	26	
Prod	6 1/4"	4 1/2"	10.5	1070'	OWC	118	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
☐ Perforate ☐ Protect Casing ☐ Plug Back TD ☐ Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	760'-762'	400 gal 7 1/2% ac, 2150# sd & 180 BBL fl	
4/2	699'-701'/670'-678'	500 gal 7 1/2% ac, 10350# sd & 400 BBL fl	

TUBING RECORD		Size	Set At	Packer At	Liner Run	Yes	✓ No
		2 3/8"	1030'	NA			
Date of First, Resumed Production, SWD or Enhr.			Producing Method				
12-3-02			Flowing ☒ Pumping ☒ Gas Lift ☐ Other (Explain) ☐				
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity		
	NA	29	29	NA	NA		

Disposition of Gas METHOD OF COMPLETION Production Interval

☐ Vented ✓ Sold ☐ Used on Lease Open Hole ✓ Perf. Dually Comp. ☐ Commingled
 (If vented, Sumit ACO-18.) ☐ Other (Specify) _____