



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS - PHONE HE1-2650

March 22, 1966

R. E. Owen
Box 153
Coffeyville, Kansas

Dear Sir:

Following are the results of tests run on the Bartlesville formation Rotary core samples taken from the Moberly Lease, Well No. 1, located in Section 24, T-31S, R-16E, Montgomery County, Kansas:

Depth, Feet	Effective	Percent Saturation			Oil Content Bbls./A.Ft.	Perm., Milli.
	Porosity Percent	Oil	Water	Total		
881.5	14.8	45	38	83	516	0.71
882.5	14.3	38	35	73	421	3.0

These samples were sealed in cans and submitted to the laboratory by the client on March 21, 1966.

Following are the results of gravity and viscosity tests run on a sample of crude oil taken from the Schultheiss Lease, Well No. 2, Montgomery County, Kansas:

Gravity 32.5° A.P.I.
Viscosity 7 cp @ 78°F.

Note: cp = centipoises

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Benjamin R. Pearman
Benjamin R. Pearman

BRP:rf
5 c.