

OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

August 26, 1980

Enutrof Production
c/o Wilkins & Wilkins
P. O. Box 707, 507 East Main
Chanute, Kansas 66720

Gentlemen:


Attached hereto are the results of tests run on the rotary core taken from the Carr Lease, Well No. 8, located in Section 3, Township 31 South, Range 16 East, Montgomery County, Kansas and submitted to our laboratory on August 19, 1980.

The core was sampled and sealed in plastic bags by a representative of the client.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES


Sanford A. Michel

SAM/ks

5 c to Chanute, Kansas

OILFIELD RESEARCH LABORATORIES

LOGName Enutrof Production Lease Carr Well No. 8

<u>Depth Interval,</u> <u>Feet</u>	<u>Description</u>
---------------------------------------	--------------------

BARTLESVILLE SAND

772.0 - 775.7	Brown shaly sandstone.
775.7 - 777.2	Brown sandstone.
777.2 - 778.3	Brown and gray laminated sandstone and shale.
778.3 - 779.0	Brown sandstone.
779.0 - 780.5	Brown shaly sandstone.
780.5 - 781.7	Gray sandy shale.
781.7 - 784.0	Gray laminated sandstone and shale.
784.0 - 785.0	Brown very shaly sandstone.
785.0 - 785.9	Gray laminated sandstone and shale.
785.9 - 786.5	Brown and gray laminated sandstone and shale.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company Enutrof Production Lease Carr Well No. 8

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	772.6	11.2	44	50	94	382	0.33
2	773.5	12.2	56	40	96	530	0.24
3	774.4	14.3	27	42	69	300	3.4
4	775.5	15.3	16	30	46	190	1.0
5	776.5	17.3	25	33	58	336	31.
6	777.3	16.7	18	21	39	233	9.6
7	778.7	18.8	25	14	39	365	29.
8	780.3	17.4	24	13	37	324	5.1
9	784.4	15.2	26	40	66	307	Imp.
10	786.2	11.1	15	64	79	129	Imp.