

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 33074
Name: Dart Cherokee Basin Operating Co., LLC
Address: P O Box 177
City/State/Zip: Mason MI 48854-0177
Purchaser: Oneok
Operator Contact Person: Beth Oswald
Phone: (517) 244-8716
Contractor: Name: _____
License: _____
Wellsite Geologist: _____
Designate Type of Completion:
____ New Well ____ Re-Entry ☒ Workover
____ Oil ____ SWD ____ SIOW ____ Temp. Abd.
☒ Gas ____ ENHR ____ SIGW
____ Dry ____ Other (Core, WSW, Expl., Cathodic, etc)
If Workover/Re-entry: Old Well Info as follows:
Operator: Zoandra Petroleum
Well Name: Wise 4A
Original Comp. Date: 7-19-85 Original Total Depth: 951'
____ Deepening ☒ Re-perf. ____ Conv. to Enhr./SWD
☒ Plug Back CIBP @ 900' Plug Back Total Depth _____
____ Commingled Docket No. _____
____ Dual Completion Docket No. _____
____ Other (SWD or Enhr.?) Docket No. _____

<u>8-1-03</u>	<u>4-21-85</u>	<u>8-29-03</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 125-27711-00-01
County: Montgomery
____ SW ____ SE ____ SW Sec. 7 Twp. 31 S. R. 16 ☒ East ☐ West
330' FSL _____ feet from S / N (circle one) Line of Section
3600' FEL _____ feet from E / W (circle one) Line of Section
Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Wise Well #: 4A
Field Name: Neodesha
Producing Formation: Penn Coals
Elevation: Ground: 814' Kelly Bushing: _____
Total Depth: 951' Plug Back Total Depth: 925'
Amount of Surface Pipe Set and Cemented at 21 Feet
Multiple Stage Cementing Collar Used? ☐ Yes ☒ No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from 928'
feet depth to surf w/ 203 sx cmt.

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)

Chloride content _____ ppm Fluid volume _____ bbls
Dewatering method used _____
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Beth Oswald
Title: Admn & Engr Asst Date: 4-30-04
Subscribed and sworn to before me this 30th day of April, 2004.
Notary Public: Karen L. Welton
Date Commission Expires: _____
Karen L. Welton
Notary Public, Ingham County, MI
My Comm. Expires Mar. 3, 2007

KCC Office Use ONLY

425 Letter of Confidentiality Attached
If Denied, Yes ☐ Date: _____
____ Wireline Log Received
____ Geologist Report Received
____ UIC Distribution

Operator Name: Dart Cherokee Basin Operating Co., LLC Lease Name: Wise Well #: 4A
 Sec. 7 Twp. 31 S. R. 16 East West County: Montgomery

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken ☐ Yes No
 (Attach Additional Sheets)

Samples Sent to Geological Survey ☐ Yes No

Cores Taken Yes No

Electric Log Run Yes No
 (Submit Copy)

List All E. Logs Run:

Log Formation (Top), Depth and Datum ☒ Sample
 Name Top Datum

RECEIVED
 MAY 03 2004
 KCC WICHITA

CASING RECORD New Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surf	8 5/8"	7"		21'	Common	3	
Prod	6 1/4"	4 1/2"	10.5#	928'	60/40	203	

ADDITIONAL CEMENTING / SQUEEZE RECORD

Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
☐ Perforate				
☐ Protect Casing				
☐ Plug Back TD				
☐ Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4 existing	910'-914' set CIBP @ 900'		
6	822'-824'	21 gal 12% HCl, 865# sd, 195 BBL fl	
6	762'-764'	21 gal 12% HCl, 110# sd, 120 BBL fl	
6	733'-738'	21 gal 12% HCl, 2300# sd, 370 BBL fl	

TUBING RECORD		Size	Set At	Packer At	Liner Run	Yes	✓ No
		2 3/8"	869'	NA			
Date of First, Resumed Production, SWD or Enhr.			Producing Method				
9-3-03			Flowing ☒ Pumping ☐ Gas Lift ☐ Other (Explain)				
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity		
	NA	0	32	NA	NA		

Disposition of Gas

METHOD OF COMPLETION

Production Interval

☐ Vented ☐ Sold ☐ Used on Lease
 (If vented, Sumit ACO-18.)

☐ Open Hole ☒ Perf. ☐ Dually Comp. ☐ Commingled
☐ Other (Specify)