

11/13
P

3-31-21E

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOG


State Geological Survey
WICHITA BRANCH

S. 3 T. 31 R. 21 E

Loc. NW NE

County Labette

640 Acres
N



Locate well correctly

Elev.: Gr. 841'

DF _____ KB _____

API No. 15 — 099 — 20,929
County Number

Operator

Hickory Creek Oil Co.

Address

P. O. Box 379 Parsons, Kansas 67357

Well No. #7

Lease Name

Wm. Devlin

Footage Location

175'

feet from N 15X line

5172 FSL 2480 FEL - KCC Record

2475'

feet from E 15X line

Principal Contractor

Carter Land & Cattle

Geologist

Chuck Robinson

Spud Date

5/4/79

Date Completed

5/8/79

Total Depth

312'

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

Eureka Crude Purchasing

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9"	7"	20 lbs	47'	portland	6	
Production	6 1/2"	4 1/2"	9 lbs	308.9'	"	100	2 sks prem. gel.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1	28g	170-196

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Gelled water sand frac. 3,500 # sand.	170-196

RECEIVED
STATE CORPORATION COMMISSION

AUG 07 1983

CONSERVATION DIVISION
Wichita, Kansas

INITIAL PRODUCTION

Date of first production 3-3-80
Producing method (flowing, pumping, gas lift, etc.) Pumping

RATE OF PRODUCTION PER 24 HOURS
Oil 9.5 bbls. Gas --- MCF Water 76 bbls. Gas-oil ratio CFPB

Disposition of gas (vented, used on lease or sold) Producing interval (s) Skinner Sand.

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator: Hickory Creek Oil Co. DESIGNATE TYPE OF COMP.: OIL GAS, DRY HOLE, SWDW, ETC.:

Well No. # 7 Lease Name W. Devlin OIL WELL

S 3 T 31 R 21 ^E/_W NW, NE

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil	0	6		
Gravel & Clay	6	25		
Lime	25	37		
Shale	37	41		
Lime	41	61		
Shale	61	121		
Lime	121	122		
Coal	122	124		
Shale & Lime brks	124	140		
Lime	140	143		
Shale-very gassy	143	163		
Sandy shale (odor) } Sand (odor)	163	169		
Shale } Change Sand } 169-240	169	181		
Lime } Sand	181	190		
Shale } Sand	190	199 240		
Shale-lots of gas	240 199	260		
Sandy shale	260	271		
Shale	271	312		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____

Signature: [Handwritten Signature]

Operations Manager _____

Title _____

July 29, 1983 _____

Date _____

2-31-91E