

**WELL COMPLETION REPORT AND DRILLER'S LOG**

**KANSAS State Geological Survey WICHITA BRANCH**


3-31-21E

S. 3 T. 31 R. 21 E

Loc. SE NW

County LABELLETTE

640 Acres N



Locate well correctly

Elev.: Gr. 839.47'

DF \_\_\_\_\_ KB \_\_\_\_\_

API No. 15 — 099 — 21,087  
County Number

Operator  
Hickory Creek Oil Co.

Address  
P.O. Box 379 Parsons, KS 67537

Well No. 25 Lease Name W. Devlin

Footage Location  
1485 feet from (N) (S) line 2145 feet from (E) (W) line

Principal Contractor J. J. Drilling Co. Geologist M. R. Gray

Spud Date 12/11/79 Date Completed 12/13/79 Total Depth 300' P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser Eureka Crude Purchasing

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9"	7"	20 lbs	47'	portland	5	
Production	6 1/2"	4 1/2"	9 lbs	287'	portland	35	1 sk prem gel

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1/2	28 g	167-187'

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
Gelled water sand frac 3500#	167-187'

**INITIAL PRODUCTION**

AUG 01 1983

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
<b>RATE OF PRODUCTION PER 24 HOURS</b>	Oil 0.8 bbls.	Gas --- MCF	Water 5.3 bbls.	Gas-oil ratio 1000	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s) Skinner sand		

RECEIVED STATE CORPORATION COMMISSION

WICHITA BRANCH DIVISION  
Wichita Gas-oil ratio 1000

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Hickory Creek Oil Co.

DESIGNATE TYPE OF COMP. OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

# 25

Lease Name

W. Devlin

S 3 T 31 R 21 <sup>E</sup><sub>XX</sub>

SE, NW

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil	0	2		
Clay	2	23		
Sand & Gravel	23	26		
Lime Broken	26	27		
Lime	27	39		
Shale sandy trace coal	39	128		
Coal	128	129		
Shale	129	135		
Lime Broken	135	145		
Shale Sandy	145	151		
Sand shaley	151	166		
Sand brown sugar, shale, coal	166	204		
Sand, trace coal,	204	234		
Coal	234	235		
Trace coal sand	235	255		
Shale sandy	255	262		
Coal	262	264		
Shale Sandy trace coal	264	300		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Operations Manager

Title

July 29, 1983

Date

3-31-91E