

KANSAS

JAN 04 1985
3-31-2/E

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 10 — 099 — 21,096
County Number

S. 3 T. 31 R. 21 ^E/_W

Loc. SE NW

County LABETTE

Operator Hickory Creek Oil Co.

Address P.O. BOX 379 Parsons, KS 67357


Well No. 28 Lease Name W. Devlin

Footage Location 1485 feet from (N) line 1815 feet from (E) (W) line

Principal Contractor J J Drilling Geologist _____

Spud Date 12/13/79 Date Completed 12/17/79 Total Depth 300' P.B.T.D. _____

Directional Deviation _____ Oil and/or Gas Purchaser Eureka Crude Purchasing



Locate well correctly
Elev.: Gr. 837.03'

DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9"	7"	20 lbs	47'	portland	5	
Production	6 1/2"	4 1/2"	9 lbs	287'	portland A	35	prem gel (1 sk)

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1/2	80 g	168 - 188

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Water frac w/3500 lb 10/20 sand	168 - 188

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) _____ Producing interval (s) Injection well

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Hickory Creek Oil Co.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. # 28	Lease Name W. Devlin	
S <u>3</u> T <u>31</u> R <u>21</u> ^E / _{WX} SE, NW		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil	0	2		
Clay	2	22		
Sand & Gravel	22	24		
Lime Broken	24	27		
Lime	27	37		
Shale Sandy lime shells	37	122		
Lime shaley broken	122	127		
Coal	127	128		
Lime broken shaley sandy	128	138		
Lime	138	140		
Lime broken	140	143		
Shale	143	146		
Coal	146	147		
Sand	147	166		
Sand	166	204		
Sand shale seams trace coal	204	242		
Shale sandy	242	261		
Coal	261	262		
Shale sandy	262	279		
Sand shaley	279	292		
Shale sandy	292	300		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	_____ Signature
	_____ General Manager Title
	_____ Date

3-31-51