

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 099 — 21,192
County Number

Operator

Hickory Creek Oil Co.

Address

Box 379 Parsons, Kansas 67357

Well No.

#56

Lease Name

Devlin

Footage Location

1485 feet from (N) (S) line

1815

feet from (E) (W) line

Principal Contractor

VW & B Drilling

Geologist

M. R. Gray

Spud Date

4-2-80

Date Completed

4-7-80

Total Depth

301'

P.B.T.D.

Directional Deviation


Oil and/or Gas Purchaser

Eureka Crude Purchasing

S. 3 T. 31 R. 21 E

Loc. NE SW

County Labette

640 Acres
N

Locate well correctly

Elev.: Gr. 838.37'

DF KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9"	7"	20 lbs	47'	portland	5	
Production	6 1/2"	4 1/2"	9 lbs	285'	portland	32	1 sk prem gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	80 g WHC	196-200'
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
X-linked gelled water 10,000# sand	196-200'
AUG 15 1983	
CONSERVATION DIVISION Wichita, Kansas	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	1.5 bbls.	MCF	33 bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
			Skinner sandstone		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

State Geological Survey
WICHITA BRANCH

Operator Hickory Creek Oil Co.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. # 56	Lease Name W. Devlin		
S <u>3</u> T <u>31</u> R <u>21</u> ^E _W		NE, SW	
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Top Soil	0	1	
Gray Clay	1	7	
Yellow Clay	7	12	
River Gravel	12	16	
Lime	16	36	
Blk. Shale	36	42	
Lt. Shale	42	43	
Lime	43	57	
Blk. Shale	57	62	
L. Shale	62	71	
Sand Stone	71	73	
Sandy Shale	73	76	
Med. Shale	76	146	
Dk. Shale	146	148	
Med. Shale -streak of coal	148	151	
Med. Shale	151	161	
Lt. Shale	161	162	
Dk. Shale	162	163	
Lime	163	164	
Dk. Shale	164	167	
Lt. Shale - streak of coal	167	175	
Lt. Shale	175	181	
Med. Shale-Sandy	181	197	
Bartlesville Sand	197	222	
Start Core 197 Stop core 217			
Broken Sand & Shale	222	238	
Med. Shale	238	265	
Dk. Shale -streak of Coal	265	272	
Lt. Shale	272	281	
Med. Shale	281	288	
Grn Shale	288	291	
Red Shale	291	292	
Grn Shale	292	301	
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	Signature Operations Manager Title August 12, 1983 Date		

3-31-91E