

Delvin Farm # 19

Sec. 3 T31S R21E
Loc. NW $\frac{1}{4}$ of NE $\frac{1}{4}$
495 feet from N.
line, 495 feet
from E. line.

Began 11-16-79 Completed 11-27-79

Drilling Contractor: VW & B Drilling Company

Drilled for Hickory Creek Oil Company

Figures indicate the bottom of formation

1	Top Soil	1	2	Dk. Shale	161
18	Lt. Clay	19	1	Lime	162
5	River Gravel	24	3	Blk. Shale	165
20	Lime	44	5	Lt. Shale	170
5	Dk. Shale	49	0	Streak of Coal	170
13	Lime	62	7	Lt. Shale	177
5	Dk. Shale	67	15	Bartlesville	
3	Lt. Shale	70		Sand Carrying	
74	Med. Shale	144		Oil	192
6	Dk. Shale	150	3	Broken Sand &	
	Trace of Coal			Shale	195
7	Dk. Shale	157	9	Med. Shale	204
2	Lime	159	0	Streak of Coal	204
			81	Med. Shale	285
			17	Grn. Shale	302

Hole size is 9 inches 29 feet 7 inches,
6 $\frac{1}{4}$ to 302 feet.

29 feet 7 inches casing set and cemented.
283 feet 3 inches; 4 inch casing with
float shoe.