

Delvin Farm # 22

Sec. 3 T31S R21E  
Loc. NW $\frac{1}{4}$  of NE $\frac{1}{4}$  825 feet  
from north line 1155  
feet from east line.

Began 12-1-79 Completed 12-3-79

Drilling Contractor VW & B Drilling Company

Drilled for Hickory Creek Oil Company

Figures indicate the bottom of formation

1	Top Soil	1	5	Lt. Shale	165
11	Yellow Clay	12	11	Med. Shale	176
5	River Gravel	17	64	Bartlesville	
10	Lime	27		Sand	240
5	Blk. Shale	32	19	Med. Shale	259
13	Lime	45	2	Dk. Shale	261
5	Blk. Shale	50	8	Lt. Shale	269
10	Lt. Shale	60	10	Med. Shale	279
90	Med. Shale	150	2	Red Clay	281
1	Lime	151	6	Grn. Shale	287
9	Med. Shale	160	15	Med. Shale	302

20 feet of 7 inch casing set with 5 sacks of cement. 286 feet 11 inches of 4 inch casing with float shoe. The bottom centerlizer set at 253 feet 4 inches. Top centerlizer set at 168 feet. Hole size 6 $\frac{1}{4}$  inches. Total depth 302 feet.