

3-31-22 E

Sec. 3 T. 31 R. 22 E

Loc. NE

County Crawford

Company

Farm Houston

No. 7

Total Depth 240


Comm. June 26, 1935

Comp. July 7, 1935

Shot or Treated

Contractor E. W. Edwards, Driller: Jas. Evans

Issued T-Dresser: W. F. Evans



Elevation

Production

|        | Casing | 10 in.     |
|--------|--------|------------|
| 20 in. |        | 10 in.     |
| 15 1/2 |        | 8 1/4 6'   |
| 12 1/2 |        | 6 5/8      |
| 13 3/8 |        | 5 3/16     |
|        |        | 6 1/4 125' |

Figures Indicate Bottom of Formation

|               |                 |
|---------------|-----------------|
| soil          | 10              |
| gravel        | 13              |
| light shale   | 65              |
| black shale   | 73              |
| light shale   | 76              |
| lime          | 81              |
| black slate   | 88              |
| light shale   | 115             |
| dark shale    | 120             |
| lime          | 123             |
| light shale   | 130             |
| light shale   | 157 show of oil |
| sandy shale   | 165             |
| sandy shale   | 173             |
| sandy shale   | 175             |
| good oil sand | 204             |
| black shale   | 205 (coal?)     |
| light shale   | 240             |

84' 4 7/8W perf. liner set on bottom of hole, 3' wkg. bbl. set 10' of bottom of pkt.

113' free oil before shot over night

100' free oil after shot over night

5 bbls. first day cleaning out

4 1/2 bbls. second day cleaning out

4 bbls. third day cleaning out

8 bbls. fourth day on beam from 10 a.m. to 4 p.m.

Note: on the log procured from Spielman the details of production before and after shot are entered in two places as has been done on this log.

Shot from 178-202 40qts.

3 bbls. before shot

5 bbls. 1st. day

4 bbls. 2nd. day

8 bbls. 3rd. day ?