

29

23131-23E

Company

Sec. 2 T. 34 R. 23 E

134

Farm *Stiles*

No.

Loc. N $\frac{1}{2}$ W $\frac{1}{2}$

34
?

Total Depth

County

Comm.

Comp.


Shot or Treated

Contractor

Issued

Drilled by Clarence Baily 1904

Casing



gw
2-6

Crawford Co

20 in.
15 1/2
12 1/2
13 3/8

10 in.
8 1/4
6 5/8
5 3/16

Elevation

Production

Figures Indicate Bottom of Formation

First water at 455, Black break

50	surface sandstone	50
18	shale, 3 coals-70', 90', 110'	130
10	oil, sandstone	140
210	shale	350
30	oil and gas, sandstone	380
15	sandstone (casing set 390)	398
57	chert and sandy lime	455
30	cotton rock	485
10	flint	495
5	blue flint	500
40	chert and cotton rock	540
60	flint	600
100	hard blue chert and limestone	700
60	white limestone, blue chert, and shells	760
5	white limestone, blue chert openings	765
10	limestone, water courses	775
18	sandstone, water	793