

LOG

15 035240950000

Company Upland Energy Lease Lewis Well No. H-1

BARTLESVILLE SAND

**RECEIVED**  
KANSAS CORPORATION COMMISSION

Depth Interval,  
Feet

Description

ORIGINAL

OCT 15 1997

3001.4 - 3002.6

Sandstone, very light grayish-brown, shaly.

CONSERVATION DIVISION  
WICHITA, KS

3002.6 - 3004.0

Sandstone, very light grayish-brown, shaly, with widely scattered mica inclusions.

3004.0 - 3006.4

Sandstone, very light grayish-brown, very shaly, with widely scattered mica inclusions.

3006.4 - 3007.4

Sandstone, light gray, very shaly, with widely scattered mica inclusions.

Note: The interval from 3004.0' to 3007.4' contains a vertical fracture.

RELEASED

OCT 13 1998

FROM CONFIDENTIAL

# OILFIELD RESEARCH LABORATORIES

RECEIVED  
LAWSON CORPORATION COMMISSION

## RESULTS OF SATURATION & PERMEABILITY TESTS

OCT 15 1997

TABLE 1

# ORIGINAL

CONSERVATION DIVISION  
WICHITA, KS

Company Upland Energy Lease Lewis Well No. H-1  
15035 240950000

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls./A.Ft.	Permeability, Millidarcys
			Oil	Water	Total		
1	3001.9	14.9	18	57	75	208	4.1
2	3002.9	13.8	16	63	79	171	3.2
3	3003.9	13.4	15	67	82	156	2.6
4	3004.8	13.9	9	57	66	95	2.8
5	3005.8	13.7	13	64	77	138	1.8
6	3006.9	13.9	8	69	77	77	2.3

RELEASED  
OCT 13 1998  
FROM CONFIDENTIAL