


THE SACO OIL CO.
King No. 1.

SEC. 22 T. 31 R. 4E.
NEc NE

Total Depth. 3041
Comm. 11-2-38 Comp. 1-8-39
Shot or Treated.
Contractor. The Saco Oil Co.
Issued. 1-28-39

County Cowley



CASING.

20" 107' 8 1/4" 2190'
15" 518'
12" 1133'
10" 1603' OR 1770'

Elevation.

Production. Dry.

Figures Indicate Bottom of Formations.

cellar	10	shale	845	lime	1980
clay	30	lime	847	sand	1985
shale	65	shale	895	sdv shale	2005
lime	75	lime	900	shale	2025
shale	90	shale	910	sand	2040
lime	115	sdv shale	920	sdv shale	2045
shale w hite	125	lime	925	sand	2070
shale light	135	shale dark	940	shale	2190
lime	140	lime hard	960	lime	2192
shale light	150	shale	990	sdv lime	2205
lime	180	lime	995	sdv shale	2220
shale	210	shale	1000	shale	2385
red rock	215	lime	1020	lime	2390
lime	230	shale	1045	shale	2400
shale blue	235	lime	1050	shale dark	2430
lime	268	shale	1070	shale light	2445
red rock	280	lime	1080	shale	2460
lime	295	shale	1132	lime	2570
shale	310	lime	1145	lime sand	2575
lime	345	slate & shells	1160	lime	2615
shale	350	lime	1195	shale blk	2635
lime	360	shale	1255	lime	2645
shale	370	lime	1320	shale light	2655
sdv shale	420	shale	1325	shale	2710
red rock	430	lime	1363	lime	2722
shale	435	shale blk	1365	shale	2755
lime	437	lime	1370	lime	2812
shale	445	shale light	1375	shale shelly	2840
lime	465	lime	1390	shale sdv	2860
shale	475	shale	1395	shale	2880
lime	490	lime	1465	shale blk	2917
shale	495	shale	1468	lime	2920
lime	500	lime	1475	shale blk	2925
shale	505	sand	1500	shale dark	2940
red rock	515	lime	1510	shale light	2950
lime	570	shale	1515	sdv slate	2960
shale	585	shale blue	1525	shale blue	2970
lime	590	shale	1527	shale dark	2980
shale	595	lime	1540	sdv shale	3006
lime	605	shale	1545	Para. iron & sandy shale	3015
shale	610	lime	1560	sdv shale	3038
lime	620	sand	1585	Top Miss lime	3038
shale	665	shale	1595	Miss lime	3041
red rock	670	lime sand	1605	Total Depth.	
lime	675	shale	1650	WATER RECORD.	
shale	715	lime	1670	3 BWP/HR 65-75	
lime	720	shale caving	1700	HFW 90-95	
shale	735	shale	1703	5 BWP/HR 782-795	
lime	740	lime shell	1705	1 1/2 BWP/HR 1330-1335	
shale	755	shale	1715	HFW 1475-1500	
lime	760	lime	1725	HFW 1575	
shale dark	775	shale	1730	water 1600	
lime	777	shale white	1765	3 BWP/HR 1765-1775	
red rock	782	lime sdv	1775	1/2 BWP/HR 2525	
sand	795	lime	1778	3 BWP/HR 2570-2575	
shale	805	shale blue	1785		
lime	810	shale	1975		