


WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY
 UNION NATIONAL BANK BLDG., WICHITA, KANSAS

22448

CASING RECORD LOCATION 300'frSL 1020'frWL SENWSE SEC 21T 31R 4E

10" 1610 FARM H.T.Hittle NO. 2 COUNTY Cowley.
 20" 96 8 1-4 1970 COMPANY The Texas Company.
 15 1-2 463 6 5-8 2072 CONTRACTOR Thayer Drilling Company.
 12 1-2 115 5 3-16 2387 COMMENCED July 2, 1927 COMPLETED Aug 28, 1927
 TOTAL DEPTH 2418 SHOT QUARTS BETWEEN



CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO The Texas Company.
 El Dorado, Kansas., ELEVATION

FIGURES INDICATE BOTTOM OF FORMATIONS.
 REMARKS 9-24-27

INITIAL PRODUCTION 30bbbls Nat.
 1st 24 hrs.

Formation	Depth	Formation	Depth.
cellar wh hard(lime stone)	6	shale grey soft	940
lime wh hard	30	lime white hard	1030
red rock red soft	35	slate grey soft	1035
slate blue soft	70	lime wh hard	1050
sdylime wh med	105	red rock red soft	1055
carried some water then could be bailed.		slate grey soft	1080
broken lime grey med	115	lime wh hard	1090
lime white hard	200	shale grey soft	1135
slate grey soft	205	lime white hard	1140
lime white hard	235	shale blue soft cavey	1150
7BWPHR 70-90 and lots of water 90-105		lime wh hd 15 1/2 1151	1160
red rock red soft	240	shale blue soft	1180
lime white hard	295	lime white hard	1205
20" casing 105		shale blue soft 6BW1320	1255
red rock red soft	300	lime wh hard	1325
lime wh hard 2BW 185	320	slate grey soft	1335
slate grey soft 3BW 255	325	lime wh hard	1375
lime white hard	380	shale blk soft	1380
slate blue soft	400	lime wh hard	1395
lime white hard	430	slate blue soft	1410
shale red rock 15 1/2 csg 463	463	lime blk hard	1430
lime wh hard	470	slate blue soft	1435
shale blue soft	475	lime dark hard	1470
lime wh hard	505	shale dark soft	1475
shale blue soft	515	lime wh hard	1500
lime white hard	520	sdylime wh med	1505
red rock red soft	525	14BWPHR	
lime white hard	535	shale blue soft	1535
slate white soft	540	lime dk hard	1538
lime white hard	590	10BW 1555. HFW 1560	
slate dark soft	595	lime broken grey med	1550
lime wh hard	600	lime sdylime wh med	1555
slate grey soft	650	lime sdylime wh hard	1605
cavey 606-630		shale blue soft	1640
lime white hard	635	10" casing 1610	
shale blue soft	670	lime wh hard cavey.	1660
lime white hard	675	shale dk soft	1700
shale dark soft	715	lime grey hard	1705
lime white hard	725	slate grey soft	1710
slate white soft	730	lime wh hard	1725
lime white hard	735	shale grey soft	1770
slate grey soft	740	lime wh hard	1780
red rock red soft	745	shale grey soft	1945
cavey 740-745		sdylime wh med	1970
lime white hard	755	HFW and 1/4 csg 1970	
shale blue soft	775	sdylime wh med	2075
lime white hard	790	shale blue soft	2385
red rock red soft	795	6-5/8 casing 2072	
cavey 790-795		sdylime med wh	2387
shale blue soft	815	broken sand med	2400
cavey 795-815		sand gas wh med	2404
lime white hard	825	sand oil brown soft	2411
slate grey soft	840	sand oil bfown soft	2418
caving bad 840		SLM TD	2418
lime white hard	845	white hard 2417-2418	
slate light soft	870		
lime white hard	890		
slate blue soft	920		
lime white hard	925		