

TYPE

★ AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

Compt. _____

SIDE ONE

(Rules 82-3-130 and 82-3-107)

DOCKET NO. NP _____

This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

F ☐ Letter requesting confidentiality attached.C ☒ Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)***Check here if NO logs were run _____.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 5054 EXPIRATION DATE 6-30-84

OPERATOR Pres-Lo, Inc. (5054) API NO. OWWO

ADDRESS P. O. Box 288 Winfield, KS 67156 COUNTY Cowley FIELD Biddle

** CONTACT PERSON M. A. Pressnall PHONE (316)782-3260 or 221-0835 PROD. FORMATION Miss/Brtvl Indicate if new pay.

PURCHASER Total Petroleum LEASE Holt C

ADDRESS Denver, CO WELL NO. 1

DRILLING Reynolds Drilling Co., Inc. 2310Ft. from South Line and
 CONTRACTOR ADDRESS 0201 College St. 330Ft. from West Line of (E)
 Winfield, KS 67156 the SW1/4Qtr.) SEC 30TWP 31 RGE 5

PLUGGING _____ (Office Use Only)
 CONTRACTOR _____
 ADDRESS _____

TOTAL DEPTH 3419 PBD 3030

SPUD DATE 2-17-56 DATE COMPLETED 8-11-83

ELEV: GR 1243 DF 1247 KB 1248

DRILLED WITH (CABLE) ROTARY (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE _____

Amount of surface pipe set and cemented 155 DV Tool Used? No

TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil Shut-in Gas, Gas, Dry, Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-completion _____. Other completion _____. NGPA filing _____.

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

AFFIDAVIT

C. DEAN PRESSNALL, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit.

State Geological Survey
WICHITA BRANCH

WELL PLAT			

KCC _____
 KGS ☒
 SWD/REP _____
 PLG. _____
 NGPA _____

Side TWO

OPERATOR

Pres-Lo, Inc.

LEASE NAME Holt C

SEC 30 TWP 31 RGE 5

(E)

(W)

WELL NO 1

FILL IN WELL INFORMATION AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.	Top	Bottom	Name	Depth
☐ Check if no Drill Stem Tests Run. ☐ Check if samples sent Geological Survey.			Stalnaker	1858
			Layton	2276
			Kansas City	2378
			Base Kans. City	2519
			Marm	2514
			Cherokee	2744
			Bartlesville	2869
			Mississippi	2961

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
300 gal. 10% NE Acid and retreat	2974-2982
1000 gal. 10% NE Acid	
750 gal 10% NE Acid	2874-2924
550 Bbl Gel Water and 80 Sacks Sand	2874-2924
Date of first production	Producing method (Flowing, pumping, gas lift, etc.)
	Pumping Gravity
Estimated Production-L.P.	Oil 8 bbls. Gas MCF Water % 100 bbls. Gas-oil ratio CFP
Disposition of gas (vented, used on lease or sold)	Perforations
Used on Lease	

Report of all strings set—surface, intermediate, production, etc.

CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additions
Surface		8 5/8		155	(O W W O)		
Production	7 7/8	5 1/2	15 lb	3030	Com	156	2% Gel 1% CaI Clor

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	3 1/8 DP	2974-2982
TUBING RECORD			2	3 1/8 DP	2914-2924
			2	3 1/8 DP	2890-2904
Size	Setting depth	Packer set at	2	3 1/8 DP	2874-2878