

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


5-31-6E

Company- H. H. BLAIR
 Farm- Eastman "A" No. 5

SEC. 5 T. 31 R. 6E
 NW SW SW SW
 625' fr SL, 360' fr WL of SW/4

Total Depth. 2888
 Comm. 11-27-54 Comp. 12-5-54
 Shot or Treated.
 Contractor. Kriswell Drilling Company
 Issued. 2-19-55

County Cowley KANSAS



CASING:

8 5/8" 99'
 5 1/2" 2886'

Elevation. 1336 K.B.

Production. 25 bbls. oil

Figures indicate Bottom of Formations.

lime	99
lime & redbed	150
shale	240
lime & sandy lime	330
lime, shale streaks	420
shale & lime streaks	1050
shale & shells	1130
shale	1210
lime & shale	1275
lime	1350
lime & shale, strks of sand	1485
lime & shale	1805
lime, sdy lime & shale	1945
shale	2170
lime & sdy shale	2208
lime	2328
shale & sand	2347
lime	2425
shale & lime	2460
lime & shale strks	2560
shale	2596
lime	2616
shale	2626
lime	2648
lime & shale	2806
sand	2810
Core #1 Sandy shale	2819
sandy shale	2823
Core #2 sand & shale	2857
sand & sdy shale	2886
lime	2888
Total depth	
Scout Tops:	
Kansas City	2163
Bartlesville	2810
Mississippi	2885