

Plotted

L.P.

JAN 29 1927

20" 10" 1560 FARM Chas. H. Eastman
 15 1-2 420 8 1-4 1936 COMPANY The Texas Company.
 12 1-2 990 6 5-8 2808 CONTRACTOR
 5 3-16 COMMENCED 11-24-26. COMPLETED 1-5-1927.
 TOTAL DEPTH 2882'.

NO. 13 COUNTY Cowley.



SHOT 40 QUARTS BETWEEN 2862-2875'

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO The Texas Company,

ELEVATION

El Dorado, Kansas.

FIGURES INDICATE BOTTOM OF FORMATIONS.

INITIAL PRODUCTION 45 bbls.

REMARKS 1/29/27.

Formation	Depth	Formation	Depth
soil yellow hard	8	lime white hrd	1515
lime white hrd	60	shale blue soft	1532
lime broken white hrd	90	red rock red soft	1536
lime broken white hrd	100	shale blue soft	1557
red rock red soft	110	red rock red soft	1575
lime white hrd	145	(Run 10" csg. at 1560')	
red rock red soft	165	shale blue soft	1580
shale gray soft	175	lime white hrd	1605
lime white hrd	180	shale blue soft	1806
lime gray hrd	250	sandy shale light sft	1875
shale gray soft	260	HFV at 1875'	
lime gray hrd	300	sand water white soft	1903
red rock red soft	330	shale white soft	1908
lime white hrd	345	sand white med.	1931
shale blue soft	380	shale blue soft	1936
red mud red soft	390	shale blue soft	2130
(Set 15 1/2" csg. at 420')		lime white hrd	2138
lime sandy white soft	426	shale blue soft	2240
shale white soft 5 BPH	440	lime white hrd	2375
lime broken white med.	450	shale blue soft	2408
shale blue soft	553	lime white hrd	2435
red beds red soft	559	sand white soft	2445
lime white hrd	564	(Water enough to drill with 2435-45')	
shale blue soft	640	lime white hrd	2475
shale blue soft	765	shale black soft	2500
lime white hrd	785	shale blue soft	2560
lime broken white med.	805	lime white hrd	2585
shale dark soft	815	shale blue soft	2612
lime white hrd	830	lime white hrd	2705
lime broken light med.	860	shale blue soft	2766
lime white hrd	890	lime shell white hrd	2776
shale blue soft	920	shale blue soft	2798
red beds red soft	925	sand white hrd	2808
shale blue soft	950	lime broken white med.	2822
(Set 12 3/4" csg. at 950')		Sand gas	2836
lime white hrd	955	(6 5/8" csg. set 2837')	
shale blue soft	990	sand gas white hrd	2840
lime shells white hrd	1010	sand oil brown hrd	2878
lime white hrd	1035	sand water white hrd	2882
lime broken white med.	1060	Slm Total Depth	2882
shale blue soft	1155		
lime white hrd	1204		
shale blue med.	1209		
lime white hrd	1225		
shale blue soft	1235		
lime white hrd	1250		
lime broken light med.	1280		
lime white hrd	1294		
shale blue soft	1338		
lime white hrd	1350		
lime broken light med.	1370		
lime white extra hard	1375		
shale blue soft	1442		
sand white med. HFV 1442-	1472		
lime white hrd 1472'	1480		
shale blue soft	1500		

Remarks:- Plugged back with lead wool to 2878' to shut off water coming in below 2878'. Well flowed natural making about 4 or 5 million feet gas, flowed 56 bbls oil from 4 P. M. Jan 4th when drilling in, stopped until 7 A. M. Jan. 5th.