

SW 7/16

6-31-JUN 1927

10" 1522
20" 8 1-4 1907
15 1-2 405 6 5-8 2848
12 1-2 980 5 3-16

FARM C. H. Eastman
COMPANY The Texas Co.
CONTRACTOR G. C. Parker.
COMMENCED 3-8-27.

NO. 14 COUNTY Cowley

COMPLETED 4-13-27.



TOTAL DEPTH 2869
CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO

SHOT QUARTS BETWEEN

The Texas Co.,

ELEVATION

INITIAL PRODUCTION 40 bbls.

El Dorado, Kansas.

FIGURES INDICATE BOTTOM OF FORMATIONS.

REMARKS 6-4-27.

Formation	Depth	Formation	Depth	Formation	Depth
cellar white hrd	6	lime white hrd	1255	Gas 2850'	
lime white hrd	50	broken lime white hrd	1315	Oil 2860' to 69'	
shale blue sft	56	shale blue sft	1325		
lime white hrd	65	lime white hrd	1345		
(2 BW at 65')		shale blue sft	1400	Total Depth	2869'.
shale blue sft	75	(HFV 1410')			
lime white hrd	100	sand white sft	1430		
red mud sft	110				
lime white hrd	120	shale blue sft	1439		
lime white hrd	130	lime white hrd	1445		
shale blue sft	135	shale white sft	1455		
lime white hrd	150	lime white hrd	1460		
red bed red sft	160	shale blue sft	1465		
lime white hrd	290	lime white hrd	1510		
red bed sft	305	shale blue sft	1520		
lime white hrd	325	lime white hrd	1526		
lime white hrd	350	shale blue sft	1534		
(6 B. W. 290')		red rock red sft	1538		
(2 BW 345-350')		shale blue sft	1544		
shale blue sft	370	red rock red sft	1555		
lime white hrd	400	lime white hrd	1580		
shale white sft	410	shale blue sft	1590		
lime white hrd	425	sandy lime white			
(Set 405' 15" csg.)		med.	1612		
(HFV 390')		shale blue sft	1725		
shale blue sft	430	(Bailing water & drilling			
lime white hrd	435	(pipe shut off)			
shale white sft	450	blue shale sft	1800		
lime white hrd	460	(u. R. 10" pipe 1522-1634'			
broken lime white		lime gray hrd	1808		
med.	490	sandy shale blue sft	1845		
shale blue sft	550	(HFV 1845')			
shale & lime shells		sand white sft	1890		
blue med.	600	sand white sft	1905		
shale blue sft	660	shale blue sft	1910		
lime white hrd	668	sand white hrd	1915		
shale white sft	700	shale white sft	2040		
sandy lime white med	720	shale blue sft	2220		
shale white sft	750	lime white hrd	2280		
lime broken white		shale blue sft	2325		
med	790	shale blue sft	2375		
lime white hrd	815	lime white hrd	2460		
shale blue sft	820	shale light sft	2540		
lime white hrd	860	lime white hrd	2555		
shale white sft	920	lime white hrd	2575		
lime white hrd	925	shale white sft	2610		
shale white sft	960	lime white hrd	2640		
lime white hrd	980	lime white hrd	2645		
(Run 12 1/2" pipe at 980')		shale black sft	2655		
shale white sft	985	lime white hrd	2668		
lime white hrd	1005	lime white hrd	2705		
shale blue sft	1010	shale light sft	2745		
lime white hrd	1030	lime white hrd	2755		
shale white sft	1060	shale blue sft	2826		
lime white hrd	1160	sandy shale light			
shale black sft	1170	sft	2843		
shale blue sft	1180	(Running 6 5/8" pipe			
lime white hrd	1190	2848 S. L. M			
lime white hrd	1230	sand light med.	2848		
shale white sft	1240	sand light sft	2869		