

UNION NATIONAL BANK BLDG., WICHITA, KANSAS.

6-31-6E

Location <sup>NE</sup> SW NE

Sec. 6 T. 31 R. 6E

990' frm SL 990' frm WL NE<sup>1</sup>/<sub>4</sub>

Casing Record

County- Cowley OCT 14 1929

20" 10" 1651 Farm- C.H. Eastman No.15  
 15" 8" 1931 Company- The Texas Co.  
 15" 415 65/8" 2851 Contr.- Parker Drlg. Co.  
 12" 976 53/16" Comm.-7-22-29 Comp.-9-4-29  
 Total Depth 2876 Shot 40, 20 Quarts Between 2866-2876  
 Correspondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formation Elevation  
 Initial Production 5 bbls.  
 Date Issued. 10-12-29

Formation	Depth	Formation	Depth
lime wh hrd	100	slate blue sft	1425
red rock red sft	105	sand gray sft HFW	1430
lime wh hrd	130	sdv lime gray hrd	1450
red mud red sft	135	slate blue sft	1475
lime wh hrd	150	lime wh hrd	1485
red mud red sft	160	brkn lime gray med.	1490
limey shale blue med.	170	lime wh hrd	1500
brkn lime blue sft	190	slate blue sft	1530
lime wh hrd	225	red rock red sft	1550
shale blue sft	260	lime wh hrd	1565
lime wh hrd	270	slate blue sft	1735
3 BWH 270-290'		shale lgt sft	1820
sdv lime wh sft	290	sdv shale lgt sft	1865
red mud red sft	300	sand lgt sft HFW	1880
lime wh hrd	370	slate blue sft	1885
slate gray sft	380	sand gray sft	1910
lime wh hrd 1 1/2 BW	410	slate blue sft	1941
limey shale gray med.	425	slate lgt sft	1960
slate blue sft	450	slate blue sft	1970
lime wh hrd	455	U.R. 8 1/4" csg & lowered to 1931'.	
brkn lime gray med.	500	shale lgt sft	1980
lime gray hrd	505	slate blue sft 1 BW	1990
slate gray sft	510	slate blue sft	2215
brkn lime gray med.	525	lime wh hrd	2340
slate wh sft	550	slate blue sft	2350
brkn lime gray med.	565	lime wh hrd	2430
lime wh hrd	575	slate blk sft	2450
brkn limegray med.	625	slate wh sft	2530
lime wh hrd	630	lime wh hrd	2545
slate blue med.	680	slate gray med.	2585
lime gray hrd	690	lime wh hrd	2660
slate blue sft	715	slate wh sft	2730
lime wh hrd	725	lime & shells drk hrd	2755
slate wh sft	750	slate wh sft	2835
lime wh hrd	760	gas sand wh sft	2855
slate blue sft	790	sand lgt sft	2876
brkn lime gray med.	800	Show Gas 2865'	
lime wh hrd	830	Show Oil 2870-76'	
slate blue sft	840		
lime & shells gray medium	970	Total Depth	2876
lime wh hrd	880		
slate wh sft	935		
lime wh hrd	940		
slate wh hrd	975		
lime wh hrd	980		
slate blue sft	985		
lime wh hrd	1005		
brkn lime gray med.	1050		
slate blue sft	1135		
lime gray hrd	1175		
brkn lime gray med.	1185		
lime wh hrd	1210		
blk slate blk sft	1215		
lime wh hrd	1225		
brkn lime gray med.	1250		
slate gray sft	1265		
lime wh hrd	1280		
slate wh sft	1300		
lime wh hrd	1320		
slate blue sft	1325		
lime wh hrd	1350		
slate blue sft	1395		
lime wh hrd	1400		