

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


Company—A. D. Mc KELVY
Farm—Ferguson No. 1

SEC. 2 T. 31 R. 8E
NE NE SW

Total Depth. 2889
Comm. 12-29-55 Comp. 1-5-56
Shot or Treated.
Contractor. White & Ellis Drilling, Inc.
Issued. 2-11-56

County Elk

KANSAS



CASING:
8 5/8 200' w/ 150 sx cmt.

Elevation. 1303 RB

Production. Dry

Figures Indicate Bottom of Formations.

soil	10
shale	16
lime	27
sandy shale w/ lime streaks	105
sand & lime	210
shale	315
shale & shells	389
shale	481
lime	501
lime & shale	560
lime	745
shale & shells	873
lime & shale	977
shale & shells	1022
lime	1028
shale & shells	1105
lime	1117
shale	1132
sand & sandy shale	1288
shale	1351
broken lime	1614
sticky shale	1731
lime	1735
sandy shale	1745
shale & sand streaks	1800
lime	2032
shale & lime	2205
lime	2261
shale & lime	2330
shale	2550
shale & shells	2551
lime	2798
shale	2840
lime	2889
Total Depth	

TOPS:	
Lansing	1351
Layton	1751
Kansas City	1800
Base K. C.	2022
Marmaton	2112
Base Marmaton	2265
Mississippi	2551
Chattanooga	2790
Arbuckle	2842

DST #1: 2696-2718, open 30 min. rec.
320' muddy SW, IFP 50#, FFP 155#,
BHP 865#/20 min.