

UNION NATIONAL BANK BLDG., WICHITA, KANSAS

Location NW SW SW (DEEPENING RECORD)
1070' frm SL & 250' frm WL SW/4

Sec. 3 T. 31 R. 8E

Casing Record

County-Elk

DEC 9 1929

10" 1355 Farm- John T. Denton No. 1
 20" 8" 1785 Company- Minnehoma Oil Co.
 15 3/8" 63 65/8" 1952 Contr.- Pennell Drlg. Co.
 12 3/8" 900 53/16" Comm.-6-17-26 Comp.-11-15-29
 Total Depth 2000 Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to

Elevation 1460 (est)

Figures Indicate Bottom of Formations.

Initial Production 200 bbls.

Date Issued. 12-7-29

Formation	Depth	Formation	Depth
lime rock	30	red rock sft	1270
mud red	40	Underreaming 10" csg.	
lime pink	45	slate lgt	1325
lime brown	60	lime sdy	1340
lime & slate	80	shale lgt	1420
slate gray	90	lime hrd	1427
lime	120	shale	1435
shale	143	slate lgt	1440
lime blue	156	lime hrd	1445
shale blue	175	slate lgt	1450
lime	185	big lime	1500
shale gray	200	salt sand	1525
lime gray	215	HFW 1500-1520'	
slate gray	240	lime hrd	1560
lime gray	260	slate sft	1565
slate gray	285	lime hrd	1625
lime	300	big lime hrd	1640
slate	450	lime hrd	1678
lime hrd	455	shale drk	1718
slate	495	lime brown	1725
slate gray sft	550	shale gray	1785
lime	600	lime brown	1786
lime hrd	625	shale brown	1812
slate	635	lime shale brkn	1822
lime gray hrd	645	shale wh	1862
slate sft	650	7 Million Gas	
lime brown hrd	670	sand	1865
slate gray sft	725	Producing Gas Sand.	
lime hrd	740	lime	1867
slate red sft	765	shale sdy	1900
lime hrd	785	lime	1905
slate	800	shells brkn	1910
lime	855	lime	1915
shale blk 1 BWPH	860	shells brkn	1950
lime hrd	864	lime brown	1952
shale red	875	Mudded Gas Sand.	
shale brown	885	lime brown	1983
slate red	900	Oil sand	2000
slate	920		
lime hrd	940	Total Depth	2000
shale blk	954		
slate gray sft	960		
lime gray hrd	970		
slate gray sft	1014		
sand wtr	1055		
slate	1070		
sand	1075		
lime	1080		
shale	1095		
slate sft	1120		
lime brown hrd	1150		
shale sft	1155		
lime hrd	1160		
shale wh sft	1170		
slate red	1175		
slate gray	1180		
slate red	1185		
red rock	1190		
slate wh	1200		
slate gray sft	1220		
lime hrd	1225		
slate wh sft	1250		
slate sft	1260		
lime shell hrd	1265		

API# 15 -

Company

Minneloma Oil

No.

1

Farm

Denton

Elev.

Location

NE SW SW

S.

3

T.

81

S.R.

8

E

County

Elk

I.P.

Was (?)

T.D.

1867

Comm.

Comp.

P.B.

Pool

Purchasing Comp.

Formation at T. D.

Pay Zone

Post Cher


Data Source:

Questionnaire

Driller's Log

Elec. Log

Plugging Aff.



State Geological Survey of Kansas

4/10/68

API# 15 -

Company

Minneloma Oil Co.

No.

1

Farm

J. I. Denton

Elev.

1402 H.R.

Location

NW SW SW

S.

3

T.

81

S.R.

8

E

County

Elk

I.P.

200 Bbls. 2M Wad

T.D.

2000

Comm.

Comp.

P.B.

Pool

Purchasing Comp.

Formation at T. D.

Pay Zone

Post Cher


Data Source:

Questionnaire

Driller's Log

Elec. Log

Plugging Aff.



State Geological Survey of Kansas

4/10/68