

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

3-31-8E


Location SW cor. NW/4

Sec. 3 T. 31 R. 8E.

Casing Record

10" 950 Farm- W. M. Ferguson No. 1
 8" 1125 Company- E. B. Shawver & S. A. Murphy.
 15 1/2" 65/8" 1550 Contr.-
 12 3/4" 53/16" 2700 Comm.- 8/19/1928. Comp.- 11/1/1928.
 Total Depth 2720'. Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to

County- Elk. DEC 15 1928



Figures Indicate Bottom of Formations.

Elevation Initial Production Dry.

Date Issued. 12/15/1928.

Formation	Depth	Formation	Depth	Formation	Depth
surface lime	20	slate	1050	shale	2260
lime	45	lime	1065	lime	2270
red rock	50	sand	1100	shale	2285
lime	65	5 BW at 1055'		lime	2290
shale	70	shale	1125	shale	2300
lime	85	HFV at 1095'		slate	2335
slate	87	shale	1175	lime	2365
lime	97	Running 8 1/2" csg. 1125'		Show of oil	
red rock	102	lime	1185	shale	2375
lime	140	slate blue	1195	lime hrd	2395
shale	145	red rock	1220	slate	2400
lime	160	lime	1230	lime	2410
shale	162	slate	1250	slate	2490
lime	180	lime	1260	lime	2492
slate	182	slate	1270	slate	2600
lime	200	red rock	1278	red rock	2602
shale	205	?	1285	slate	2638
lime	220	slate	1295	lime sandy	2640
slate	235	red rock	1298	slate	2700
slate	245	lime	1300	Run 5 3/16" csg. 2700'	
lime	250	slate	1325	Miss. lime	2715
slate	285	shale light	1340	lime	2720
lime	290	shale brown	1350		
slate	305	shale gray	1410	Total Depth	2720'
lime	315	shale blue	1440		
slate	340	shale brown	1455		
lime	345	lime hrd	1458		
slate	405	lime	1460		
lime	410	slate	1490		
shale	430	lime big	1540		
slate	460	lime big lime	1550		
lime	465	Set 6 5/8" csg. at 1550'			
slate	480	lime big lime	1648		
lime	485	lime big lime	1655		
slate	490	Underrcamed 6" to 1655'			
lime	500	big lime	1695		
slate	520	slate	1720		
lime	530	slate	1735		
shale	540	lime	1740		
lime	560	slate	1870		
slate	647	lime	1875		
lime	670	slate sandy	1910		
shale	680	gas sand	1933		
lime	695	Oswego lime	1985		
slate	705	slate	1989		
lime	715	lime	1997		
slate	735	slate & shells	2018		
lime	745	lime	2027		
shale	785	slate	2032		
lime	792	lime	2065		
shale	800	lime	2075		
lime	872	lime	2105		
slate	875	slate black	2112		
lime	895	lime hrd	2125		
slate	900	lime hrd	2150		
red rock	910	lime	2163		
lime	920	slate	2175		
shale	958	lime	2181		
Running 950' of 10" csg.		shale	2188		
lime	970	lime	2205		
slate	980	shale	2210		
lime	990	slate	2245		
black slate	1010	lime	2250		