

8-32-1E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- LARIO OIL & GAS COMPANY
Farm- Rusk "B" No. 2

SEC. 8 T. 32 R. 1E
SE NW NE

Total Depth. 4032'
Comm. 2-19-60 Comp. 3-12-60
Shot or Treated.
Contractor. Prime Drilling Company
Issued. 8-13-60

County Sumner
KANSAS



CASING:

10 3/4" @ 443' w/450 sks. cem.
5 1/2" @ 4028' w/75 sks. cem.

Elevation. 1254' DF

Production. 46 BBLS oil &
5 BBLS water

Figures indicate Bottom of Formations.

shale & shells	275
lime & shale	310
lime	1060
shale & lime	2390
shale	2530
lime & shale	2650
shale & lime	2697
shale	2946
lime	3180
lime & shale	3582
Mississippi lime	3591
cherty lime	3674
Mississippi lime	3712
cherty lime	3779
Mississippi lime	3812
cherty lime	3950
lime	4006
shale	4027
shale	4030 RTD
sand	4032
Total Depth	

TOPS:

Brown lime	2619
Stalnaker Sand (Shaly)	2645
Stalnaker Sand (Clean)	2656
Base Stalnaker Sand	2685
Kansas City Limestone	2947
Base Kansas City	3196
Cleveland Sand	3243
Base Cleveland Sand	3259
Marmaton	3289
Cherokee	3431
Mississippi Chert	3582
Mississippi Lime	3586
Chattanooga Shale	3994
Simpson Sandstone	4027