

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG, WICHITA, KAN SAS

DEEPENING RECORD

Location C SL SE SW.
220' SL 660' EL SW/4

Sec. 1 T. 32 R. 10E

Casing Record

County- Chautauqua.
No. 8

10" 682'. Farm- Oliver
20" 8 1/2" Company- Griffin & Bell.
15 3/4" 65/8" Contr.- Lee Tippie.
12 3/4" 298 53/16" Comm.- 7-9-30.

Comp.- 10-1-30.

Total Depth 2293'9" Shot Quarts Between
Correspondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formations.

Initial Production

Date Issued. 6-5-37

102 bbls 1st 24 hrs.
82 bbls 2nd 24 hrs.

Elevation

Formation	Depth	Formation	Depth
soil	2	shale black	1357
clay	7	lime	1390
sand	11	shale black	1412
lime	18	lime	1422
shale	23	shale	1465
lime	29	lime	1475
shale	33	shale black	1480
lime	55	lime hrd	1495
shale	60	shale black	1502
lime	62	sand SIM	1540
shale	75	sdv shale	1581
sdv shale (2 BW	110	shale black	1583'6"
shale in 24 hrs)	125	lime	1585'6"
lime	140	shale black	1586'6"
shale	146	shale white	1589
lime	151	lime	1590
shale	159	Top Pawnee	
red rock	172	lime grey	1596
shale	225	lime	1618
sand	235	shale black	1628
sdv shale	270	shale white	1638
sand	285	S.L.M.	
shale	288	Top Oswego	
sand 1 1/2 blr. wtr.	293	lime pay	1664
shale	304		
lime	326	TD	1664'
shale black	330		
lime	335	Filled up 600' in 8" hole in	
shale	345	3 hrs. 39 gravity oil.	
sand HFV	373		
shale	378	(OVER)	
red rock	390		
shale	395		
lime	400		
shale	470		
sand	495		
shale	617		
shale black	621		
lime	626		
shale	645		
sdv shale	665		
sand	675		
shale	943		
lime	963		
shale	1098		
sand	1118		
shale	1135		
sand 10 BW	1145		
sdv shale	1170		

DEEPENING RECORD

Comm. 3-31-37 Comp. 4-21-37
 Prod. 50 Bbls.

Old T. D. 1664'

no log	1664 -1665
shale black	1665 -1669
lime	1677
shale	1683
lime	1687
shale	1795
lime pink	1805
shale	1850
red rock	1862
shale drk	1907
red rock	1917
shale	1968

Top Miss lime 1968

lime hrd	1973
lime sft	1977
lime hrd sharp	2004
lime sft	2008
lime hrd	2037
lime sft	2159

6 5/8" 2010'

Show oil 2037-2045

lime black & hrd	2184
lime black sft	2205
lime grey hrd HFW	2248

Top of Chattanooga shale 2248

shale black hrd	2291
Siliceous cap rock hrd	2292

5 3/16" 2271' SIM

1st show of oil 2292

lime firm	2293
lime sft	2293'9"

Hole started to fill up

Total Depth.