

Harold Peterson Farm

Sec. 10 T32 R 18  
Loc. NE $\frac{1}{4}$  NW $\frac{1}{4}$  400 ft. from  
N. fence, 660 ft. from  
W. fence  
County: LaBette

Gas Well

Depth 675 ft.

Commenced 8-27-79 Completed 9-1-79

Drilling Contractor; VW & B Drilling Company  
Box 7  
Cherryvale, Kans. 67335

Figures indicate the bottom of formation

1	Top Soil	1	10	Lime	495
58	Shale	59	5	Blk Shale (Gas)	500
2	Lime	61	140	Shale	640
91	Shale	152	10	Sand-Bartlesville	650
4	Lime	156	15	Broken Sand	665
1	Shale (green)	157	5	Sand (Brown)	670
11	Lime	168	5	Sand (Broken)	675
12	Shale	180			
12	Lime	192			
4	Shale	196			
4	Lime	210			
10	Shale	220			
5	Sand	225			
105	Shale	330			
25	Pink Lime	355			
10	Blk Shale	365			
53	Shale	418			
27	Oswego Lime	445			
10	Blk Shale (Gas)	455			
25	Lime	480			
5	Blk Shale(Gas)	485			

Hole Size 9" to 20 ft.  
6 $\frac{1}{4}$ " to 675 ft.

7" Casing 21 $\frac{1}{2}$  ft.  
Packer set at 627 ft.  
Lead seat in packer to accomodate 1"  
seating nipple. 2 $\frac{1}{2}$ " upset pipe.