


Company- CYMCO PETROLEUM COMPANY
Farm- Overman No. 1

SEC. 10 T. 32 R. 7E
NW NE SW

Total Depth. 2894'
Comm. 5-26-58 Comp. 6-8-58
Shot or Treated.
Contractor. Gearhart-Canaday Drlg. Co.
issued. 8-23-58

County Cowley
KANSAS



CASING:

Elevation. 1381' DE

8 5/8" 139' cem. w/150 sx.
5 1/2" 2894' cem. w/100 sx.

Production. 75 BOPD

Figures Indicate Bottom of Formations.

surface soil & gravel	2	
lime	80	
lime & shale	285	
shale w/lime	500	
shale w/lime strks.	830	
shale	1029	
shale w/lime strks.	1130	
sand & shale	1225	
shale	1420	
shale & sand	1625	
sdv shale	1780	
shale & lime	1860	
shale w/lime & sand		
stringers	2060	
sand & sdv shale	2098	
sand (good odor)	2140	
shale & sand	2241	
lime & shale	2265	
lime w/shale	2395	
lime	2435	
sand	2440	
shale & lime	2790	
shale-sand	2802	
sand	2825	(good show free oil)
sand	2827	
shale	2838	
shale & lime	2888	
lime	2894	(good show oil) RTD
Total Depth		

Tops: (Scout)

Layton Zone	2061
Layton Sand	2098
Kansas City	2248
Cleveland	2404
Oswego	2534
Bartlesville	2800
Mississippi	2870

Perforated 2804' - 2810' w/24 holes.
Swb. 5 BOPH & trace water natural.