

WELL LOG

Well No. 4
 Farm - DeBolt
 County - Labette

FR. W $\frac{1}{2}$ SE $\frac{1}{4}$
 Sec. 24
 Twp. 32
 Rge. 17

Producer - Dodson Drilling Co.
 Completed - August 1972

24-32-NE

Thickness of Strata	Formation	Depth
16	Soil and Clay	16
7	Sand and Gravel	23
3	Lime	26
16	Black Sdy Shale	42
3	Lime	45
10	Shale	55
3	Lime	58
9	Shale	67
2	Lime	69
34	Shale	103
7	Lime	110
3	Shale	113
3	Lime	116
4	Shale	120
2	Lime	122
9	Shale	131
12	Lime	143
4	B. Shale	147
14	Lime	161
27	Sdy Shale	188
9	Sand	197
2	Lime	199
9	Sand	208
22	Shale	230
14	Sand	244
28	Sdy Shale	272
26	Lime (pink)	298
11	D. Shale	309
2	Lime	311
57	Shale	368
35	Lime (oswego)	403
7	Slate	410
22	Lime	432
5	Shale and Slate	437
9	Lime (5ft.)	446
45	Shale	491
3	Lime	494
4	Shale	498
3	Lime	501
54	Shale	555
2	Lime	557
55	Shale	612
18	L. Sand	630
4	Shale	634
4	Gray Sand	638
5	D. Shale	651
3	Black Sand	654
5-3	Oil Sand - Brown	659.3
4-2"	Black Sand	663.5

Water From 16 to 24 feet
 26' 8" Drive Pipe

2 Bailer Water per Hr.
 From 143 to 147

Oil odor and Scum 200

Set 7" @ 448

Run S. L. @ 656.6"

Plugged back to 654.5 with Chat
 Set 4" casing at 654.5 and cemented to surface
 Drilled out Rock and cement To 663.5. T. D.