


11-32-2E

WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY
UNION NATIONAL BANK BLDG., WICHITA, KANSAS

CASING RECORD

LOCATION Lot 16, Block 35, 155' E of **SEC 11 T 32 R 2 E.**
 C Osage Street, 161' S of C. Myrtle St.

10" 1145 **FARM** Community **NO. 3 COUNTY** Summer
 20" 26 8 1-4 1424 **COMPANY** Roxana Petroleum Corp.
 15 1-2 102 6 5-8 1955 **CONTRACTOR**
 12 1-2 5 3-16 2046 **COMMENCED** 8-17-27. **COMPLETED** 10-5-27.
TOTAL DEPTH 2120' **SLM** **SHOT** **QUARTS BETWEEN**
CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO



FIGURES INDICATE BOTTOM OF FORMATIONS.
REMARKS 11/5/27.

ELEVATION
INITIAL PRODUCTION 500 bbls.
 (Scout ticket)

Formation	Depth	Formation	Depth
red clay	25	blue slate	1170
sand	37	white shale	1190
slate	58	slate	1195
sandy lime HFW	60	blue shale	1215
slate	120	lime	1225
lime	140	2 BW H at 1215'	
slate	145	blue shale	1240
lime	150	lime	1245
blue slate	160	shale	1305
red rock	170	sandy lime HFW 1310'	1320
slate	175	lime	1340
lime	205	slate	1345
slate	220	lime	1350
lime	230	slate	1378
shale	270	sand	1382
lime	330	lime	1395
blue slate	365	slate	1418
red rock	375	lime	1430
slate	390	slate	1435
shale	395	lime	1495
lime	415	sandy lime 1 1/2 BW PH	1500
blue shale	425	lime	1550
red rock	435	shale	1555
blue slate	470	lime	1570
lime	485	shale	1580
blue shale	495	lime	1675
lime	500	shale	1695
blue slate	545	lime	1705
lime	570	shale	1780
red rock	590	slate	1800
blue slate	600	lime	1815
lime	655	shale	1875
shale	665	white shale	1900
lime	670	lime	1905
white shale	680	shale	1935
lime	695	sand 2 BW PH	1940
sandy lime 4 BW H	710	shale	2000
lime	740	white shale	2040
shale	745	black shale	2051
lime 6 BW H	825	brown lime	2053
white shale	840	Steel line correction	2048
blue shale 3 BW H	895	lime	2049
lime	900	shale	2054
shale	920	sand	2059
lime	945	Show oil M. hrd coarse.	
shale	970	sand some shale	2075
blue shale	1010	Good wash	
lime	1015	sandy lime inc. O. & G.	2077
white shale	1040	sand good wash	2082
shale	1070	sand & shale	2092
lime	1090	Steel line correction	2085
3 BW H at 1080'		sand & shale	2120
blue shale	1115	900' oil in hole	
sandy lime	1125	Total Depth SLM	2120
Show oil FU 100' in 30 min.			
lime	1129		
blue shale	1132		
lime	1145		