

WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY
UNION NATIONAL BANK BLDG., WICHITA, KANSAS

CASING RECORD

LOCATION 927' S CL Santa FE R. R.,


SEC 14T 32 R 2 E.

639' fr WL SE/4

NO. 7 COUNTY

Summer.

20" 87 10" 1352 FARM Emrich
 15 1-2 390 8 1-4 1780 COMPANY Roxana Petroleum Corp.
 12 1-2 970 6 5-8 1992 CONTRACTOR
 5 3-16 COMMENCED 11-25-27. COMPLETED 12-18-27.
 TOTAL DEPTH 2096' SLM SHOT QUARTS BETWEEN
 CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO



ELEVATION

INITIAL PRODUCTION 1809 bbls.

FIGURES INDICATE BOTTOM OF FORMATIONS.

REMARKS 1/14/28.

Formation	Depth	Formation	Depth
cellar	8	lime hard	1170
clay	25	lime	1175
sand	40	shale	1180
blue shale	50	lime	1195
10' of 24" conductor.		red rock	1198
lime 20" 87'	60	shale	1208
blue shale	110	lime	1210
sand water	125	Rainbow show oil at 1210' &	
blue shale	150	2 BW PH	
light shale	160	shale	1220
sand HFV	175	shale harder	1230
shale light	280	sandy shale black	1296
sandy lime	310	SLM at 1296'	
light shale	340	sandy lime Topeka	1301
red rock	350	sandy lime	1306
light lime	360	No oil or water.	
light shale	370	sandy lime	1311
sandy lime	390	No water-No oil	
15 1/2" 390'		sandy lime	1334
shale	395	No oil no water	
lime	400	sandy shale	1340
red rock	415	Inc. in water.	
shale	430	sandy shale	1345
light shale	440	shale 10" 1348'	1347
lime	460	blue shale	1351
blue shale	470	lime	1356
lime	490	shale	1370
light shale	500	lime	1375
lime	505	shale	1400
light shale	515	lime	1445
lime	545	shale	1450
red rock	570	lime	1475
light shale	575	shale	1485
lime	610	lime	1555
shale	615	shale blue	1570
sandy lime 3 BW PH	630	blue shale	1595
lime	635	lime	1600
dark shale	650	shale	1620
lime	660	lime	1625
light shale	675	shale	1640
sandy lime 5 BW PH	695	sand 15 BW PH	1645
blue shale	700	blue shale	1720
lime	715	lime	1735
blue shale	720	blue shale	1740
lime	745	lime	1765
shale	750	sandy shale dry	1775
lime	760	lime	1795
shale	810	shale	1825
lime	820	shale	1835
shale	840	shale	1880
blue shale	950	lime	1895
sand HFV	965	light shale	1980
blue shale	980	dark shale	1991
grey lime	985	6 5/8" 1992'	
limey shale	1030	lime Cable meas.	1992
lime	1035	sandy lime	2032
shale	1070	SLM at 2032'	
lime	1075	1st show oil 2005-2015'	
shale	1085	Free oil 2015-2020'	
blue shale	1090	sand & shale	2096
lime 1 BW PH	1125	Inc. oil & show gas 2074-96'	
blue shale	1160	SLM at 2096'	
		Total Depth SLM	2096'