

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
Union National Bk Bldg, Wichita, Kansas.


T.M. DEAL OIL & GAS CO.
Marrs-Oxford No. 1.

SEC. 14 T. 32 R. 2E
Block 35 Lot 11

Total Depth. 3051'
Comm. 2-24-36 Comp. 4-14-36
Shot or Treated. 3000 Gals. acid
Contractor.
Issued. 5-2-36.

County. Sumner

CASING.
15 1/2" 248'
6 5/8" 2918'
5 3/16" 148' 10" (liner)



Elevation.

Production. Pot. 1060 Bbls
Bbls. 24 hrs.

Figures Indicate Bottom of Formations.

surface clay & sand	40
lime-shale	155
lime shale	225
shale & shells	248
shale & shells	398
shale-shells	415
red bed	422
shale & shells	799
sandy shale & shells	986
shale & shells	1225
lime shale	1325
broken lime & shale	1506
lime	1635
lime shale	1715
lime hard & shale	1760
shale & hard lime	1802
shells	1802
lime shale	1875
lime & shale	1921
broken lime & shale	1973
shale	2039
lime shale & sand	2079
Top stalnaker	2048
sand & shale	2130
shale	2465
K.C.lime	2525
lime	2626
broken lime shale	2670
shale	2672
lime & shale	2693
broken lime shale	2755
shale & lime hard	2786
lime & shale-	2824
broken lime	2845
shale black	2855
shale & lime	2874
shale & line	2897
Chatanooga shale	2916
shale	2993
Wilcox sand	3030
dolomite	3051
Total Depth.	